

Department of Energy

Portsmouth/Paducah Project Office 1017 Majestic Drive, Suite 200 Lexington, Kentucky 40513 (859) 219-4000

JUL 3 1 2018

Mr. Norm Sandlin, Prime Contract Manager Four Rivers Nuclear Partnership, LLC 5511 Hobbs Road Kevil, Kentucky 42053 PPPO-02-4895956-18A

Dear Mr. Sandlin:

CONTRACT NO. DE-EM0004895: APPROVAL OF DELIVERABLE NO. 43, GROUNDWATER PROTECTION PLAN, PAD-PROJ-0018/FR2

Reference: Letter from M. Redfield to M. Fultz, "Four Rivers Nuclear Partnership, LLC— Deliverable No. 43—Transmittal of the *Groundwater Protection Plan for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky*, PAD-PROJ-0018/FR2," (FRNP-18-1027), dated July 23, 2018

The U.S. Department of Energy approves the Four Rivers Nuclear Partnership, LLC, Deliverable No. 43, Groundwater Protection Plan, PAD-PROJ-0018/FR2.

If you have any questions or require additional information, please contact David Dollins at (270) 441-6819.

Sincerely,

Marcia D. Fultz Contracting Officer Portsmouth/Paducah Project Office

e-copy:

april.ladd@pppo.gov, PPPO brandy.mitchell@pad.pppo.gov, FRNP bruce.ford@pad.pppo.gov, FRNP cory.hicks@pad.pppo.gov, FRNP curt.walker@pad.pppo.gov, FRNP daniel.lillard@pppo.gov, PPPO dave.dollins@pppo.gov, PPPO frnpcorrespondence@pad.pppo.gov, FRNP james.miller@pad.pppo.gov, FRNP jennifer.blewett@pad.pppo.gov, FRNP jennifer.woodard@pppo.gov, PPPO joel.bradburne@pppo.gov, PPPO

joseph.stanley@pad.pppo.gov, FRNP karen.testerman@pppo.gov, SMSI karen.walker@pad.pppo.gov, FRNP kelly.layne@pad.pppo.gov, FRNP kim.knerr@pppo.gov, PPPO larry.glover@pad.pppo.gov, FRNP marcia.fultz@pppo.gov, PPPO myrna.redfield@pad.pppo.gov, FRNP norm.sandlin@pad.pppo.gov, FRNP pad.rmc@pad.pppo.gov, SSI robert.edwards@pppo.gov, PPPO tracey.duncan@pppo.gov, PPPO

PAD-PROJ-0018/FR2

Groundwater Protection Plan for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky



CLEARED FOR PUBLIC RELEASE

PAD-PROJ-0018/FR2

Groundwater Protection Plan for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky

Date Issued—July 2018

Prepared for the U.S. DEPARTMENT OF ENERGY Office of Environmental Management

Prepared by FOUR RIVERS NUCLEAR PARTNERSHIP, LLC, managing the Deactivation and Remediation Project at the Paducah Gaseous Diffusion Plant under Contract DE-EM0004895

CLEARED FOR PUBLIC RELEASE

THIS PAGE INTENTIONALLY LEFT BLANK

FI	GURE	S	v
TA	BLE.		v
AC	CRON	YMS	vii
ЕΧ	KECU	TIVE SUMMARY	ix
1.	GEN	JERAL INFORMATION	1
2.	PHY	SICAL CHARACTERISTICS	
	2.1	GEOMORPHOLOGY	
	2.2	SITE GEOLOGY	
	2.3	SITE HYDROLOGY	
3.	ACT	TIVITIES THAT HAVE THE POTENTIAL TO POLLUTE GROUNDWATER	11
4.	PR A	CTICES SELECTED TO PROTECT GROUNDWATER FROM POLLUTION	17
	4.1	INTEGRATED SAFETY MANAGEMENT SYSTEM AND ENVIRONMENTAL	
		MANAGEMENT SYSTEMS	
	4.2	GROUNDWATER MONITORING	
		4.2.1 RCRA Subtitle C Monitoring	
		4.2.2 Underground Storage Tank Monitoring	19
		4.2.3 RCRA 3004 (u/v) and CERCLA Monitoring	19
		4.2.4 RCRA Subtitle D Landfill Groundwater Monitoring	
		4.2.5 Monitoring Well Preventive Maintenance	
		4.2.6 Evaluation of Floor Drains	
		4.2.7 Evaluation of Loading and Unloading Areas	
	4.3	ENVIRONMENTAL SURVEILLANCE MONITORING	
	4.4	KENTUCKY POLLUTANT DISCHARGE ELIMINATION SYSTEM OUTFALLS	
	4.5	SAMPLE COLLECTION	
		4.5.1 Surface Water [401 <i>KAR</i> 5:037 § 2(2)(0)]	
		4.5.2 Surface and Subsurface Soil [401 <i>KAR</i> 5:037 § 2(2)(m)]	
	1.0	4.5.3 Well Sampling [401 <i>KAR</i> 5:037 § 2(2)(m)]	
	4.6	SUBSURFACE PENETRATIONS [401 KAR 5:037 § 2(2)(m)]	
	4.7	STORAGE OF BULK QUANTITIES OF MATERIALS, RECYCLABLES, AND	25
		WASTES [401 <i>KAR</i> 5:037 § 2(2)(a), (g), & (j)] 4.7.1 Fuel Storage Tanks	
		4.7.1 Fuel Storage Tanks	
		4.7.2 Used Off	
		4.7.4 Storage of UF_6	
		4.7.4 Storage of Or 64.7.5 Storage of Aqueous Hydrogen Fluoride	
		4.7.6 Storage of Posi-Shell [®] Chemicals	
		4.7.7 Storage of Flocculants	
		4.7.8 Storage of Road Oils and Deicing Materials	
		4.7.9 Storage of Herbicides and Pesticides	

CONTENTS

4.8	WAST	E MANAGEMENT [401 KAR 5:037 § 2(2)(f)]	
	4.8.1	Release Prevention and Control	
	4.8.2	Release Control	
4.9		RIAL TRANSFERS [401 KAR 5:037 § 2(2)(p)]	
4.10		TMENT	
		Groundwater [401 KAR 5:037 § 2(2)(n)]	
	4.10.2	Decontamination, Well Development, and Well Purge Wastewater	
		[401 KAR 5:037 § 2(2)(n)]	
		C-746-S and C-746-U Landfill Leachate [401 KAR 5:037 § 2(2)(n)]	
		Miscellaneous Wastewater [401 KAR 5:037 § $2(2)(n)$]	
		Noncontact Cooling Water [401 <i>KAR</i> 5:037 § $2(2)(n)$]	
		C-613 Storm Water Control Basin [401 <i>KAR</i> 5:037 § 2(2)(0)]	
	4.10.7	Use of Surface Impoundments, Lagoons, Ditches in CERCLA Projects	21
		[401 KAR 5:037 § 2(2)(o)]	
5. IMPI	LEMEN	TATION SCHEDULE	
6. EMP	LOYEE	TRAINING	
7. INSF	PECTIO	N SCHEDULE	
8. CER'	TIFICA	TION STATEMENT	
9. REV	IEW LC	OCATION FOR GROUNDWATER PROTECTION PLAN	
10. REF	ERENC	ES	
APPEND	DIX A:	DOE PADUCAH SITE FIGURES AND TABLE	A-1
APPEND	DIX B:	U.S. DEPARTMENT OF ENERGY CONTRACTOR PROCEDURES	B-1

FIGURES

1.	Reasonably Anticipated Future Land Use at PGDP	4
2.	Current Land Use at PGDP	5
3.	Lithostratigraphic Column of the Jackson Purchase Region	6
	Schematic of Stratigraphic and Structural Relationships near PGDP	
5.	KPDES Outfall Locations at PGDP	23

TABLE

1.	Summary Information on USTs	20)
----	-----------------------------	----	---

THIS PAGE INTENTIONALLY LEFT BLANK

ACRONYMS

amsl	above mean sea level
AOC	area of concern
BMP	Best Management Practices Plan
CAT	Consolidated Annual Training
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
D&R	deactivation and remediation
DOE	U.S. Department of Energy
EMP	Environmental Monitoring Plan
EPA	U.S. Environmental Protection Agency
ERH	electrical resistance heating
ERPP	Environmental Radiological Protection Program
FFA	Federal Facility Agreement
FRNP	Four Rivers Nuclear Partnership, LLC
GET	General Employee Training
GPP	Groundwater Protection Plan
KAR	Kentucky Administrative Regulations
KDEP	Kentucky Department for Environmental Protection
KDWM	Kentucky Division of Waste Management
KPDES	Kentucky Pollutant Discharge Elimination System
LCD	Lower Continental Deposits
MCS	Mid-America Conversion Services, LLC
MW	monitoring well
NFA	no further action
PGDP	Paducah Gaseous Diffusion Plant
RACR	remedial action completion report
RCRA	Resource Conservation and Recovery Act
RGA	Regional Gravel Aquifer
ROD	record of decision
SPCC	Spill Prevention, Control, and Countermeasure Plan
SST	Swift & Staley Team
SWMU	solid waste management unit
TPD	training position description
UCD	Upper Continental Deposits
UCRS	Upper Continental Recharge System
USEC	United States Enrichment Corporation
UST	underground storage tank
VOC	volatile organic compound

THIS PAGE INTENTIONALLY LEFT BLANK

EXECUTIVE SUMMARY

The U.S. Department of Energy (DOE) prepared and began implementation of a Groundwater Protection Plan (GPP) in August 1995 for the Paducah Gaseous Diffusion Plant (PGDP). This document presents the revision to the 2015 version of the Groundwater Protection Plan (LATA 2015). Stated in 401 *KAR* 5:037 § 4(3) is the following requirement regarding the review of the GPP:

Each groundwater protection plan shall be reviewed in its entirety every three (3) years, by the persons responsible for the plan, updated if necessary, and recertified. To the extent possible, the review shall include a reevaluation of the design and operation procedures for the pollution prevention practices previously selected for the plan to ensure that they are effective.

This GPP incorporates revisions resulting from the three-year review required by 401 *KAR* 5:037 § 4(3). This document addresses the following specific requirements listed in 401 *KAR* 5:037 § 3(3) and the guidance document relating to 401 *KAR* 5:037 § 3(3)(a) through (g) (*Preparing a Groundwater Protection Plan*, KDEP 2018): (1) general information regarding the facility and its operation; (2) identification of activities associated with the facility as identified in Section 2(2) of the regulation; (3) identification of all practices chosen for the plan to protect groundwater from pollution; (4) implementation schedules for the protection practices; (5) description of and implementation schedule for employee training necessary to ensure implementation of the plan; (6) schedule of required inspections, as applicable to ensure that all practices established are in place and properly functioning; and (7) certification of the plan by the appropriate Paducah Site representative and that the person responsible for implementing the plan has reviewed the terms of the plan and will implement its provisions.

This revision includes changes to reflect the return and management of formerly leased facilities from the United States Enrichment Corporation to DOE, the orderly and systematic shutdown of Paducah Site operations, and transition to a new Deactivation and Remediation Contractor.

THIS PAGE INTENTIONALLY LEFT BLANK

1. GENERAL INFORMATION

This Groundwater Protection Plan (GPP) has been written in accordance with 401 *KAR* 5:037 to ensure protection for all current and future uses of groundwater and to prevent additional groundwater pollution at the following facility.

Name and Address of Facility

Paducah Gaseous Diffusion Plant 5600 Hobbs Road Kevil, Kentucky 42053 McCracken County latitude 37°6'41.95" and longitude 88°48'46.09"

Person Developing GPP

Program Manager Four Rivers Nuclear Partnership, LLC 5511 Hobbs Road Kevil, Kentucky 42053 Phone: (270) 441-6412

Person Responsible for Implementing GPP

Manager Portsmouth/Paducah Project Office U.S. Department of Energy 1017 Majestic Drive, Suite 200 Lexington, Kentucky 40513 Phone: (859) 219-4010

This plan will be implemented under the direction of the U.S. Department of Energy (DOE) Manager, Portsmouth/Paducah Project Office, and is applicable to activities performed by DOE and its contractors/representatives at the Paducah Gaseous Diffusion Plant (PGDP). In support of DOE, this plan was developed by Four Rivers Nuclear Partnership, LLC, (FRNP) and is implemented by DOE and its current contractors:

- DOE, 5501 Hobbs Road, Kevil, Kentucky 42053, (270) 441-6800
- FRNP [Deactivation and Remediation (D&R) Contractor], 5511 Hobbs Road, Kevil, Kentucky 42053, (270) 441-6412
- Swift & Staley Inc. (Infrastructure Contractor), 5505 Hobbs Road, Kevil, Kentucky 42053, (270) 441-5270
- Mid-America Conversion Services, LLC, [Depleted Uranium Hexafluoride (DUF₆) Contractor] 1020 Monarch Street, Suite 300, Lexington, Kentucky 40513, (859) 685-9268

As required by 401 *KAR* 5:037 § 4(3), this GPP is to be reviewed every three years. Records associated with GPP implementation [e.g., Resource Conservation and Recovery Act (RCRA) facility inspections, C-404 sump integrity tests, storm water inspections, waste inspections] will be retained for a period of at least six years after their preparation. Reference documents listed herein are available through the U.S. Department of Energy Paducah Environmental Information Center (EIC) located at 5100 Alben

Barkley Drive, Emerging Technology Center, Room 221, Paducah, Kentucky, or the website, <u>http://www.paducaheic.com</u>. Records of GPP activities are maintained under other programs, as identified in Section 4 of this Plan.

Brief Description of Facility. The Paducah Site is located in western Kentucky and includes PGDP, a former uranium enrichment facility owned by DOE. Since its initial operation in 1952, the Paducah Site's primary function was the enrichment of the fissionable isotope uranium-235 from natural assay uranium using a gaseous diffusion process with uranium hexafluoride (UF₆). Plant activities have included utility, laboratory, and maintenance support; conversion of uranium dioxide to UF₆ (to feed the diffusion process) and uranium tetrafluoride; metal production from depleted UF₆; and uranium metal processing, metals recovery, and other small operations performed for DOE and the U.S. Department of Defense such as precision machining and protective metal coating application. The Paducah Site also has an enrichment cascade housed in four large process buildings, four sets of cooling towers, phosphate reduction facility, and sanitary and potable water treatment plants.

In August 1988, volatile organic compounds (VOCs) and radionuclides were detected in private water wells north of the Paducah Site, which was placed on the National Priorities List in 1994. Since 1998, DOE, U.S. Environmental Protection Agency (EPA), and Kentucky Department for Environment Protection (KDEP) have been operating under the Federal Facility Agreement (FFA), with DOE as the lead agency and EPA and KDEP as support agencies providing oversight. The D&R Contractor works with DOE to remove/mitigate past contamination at the Paducah Site.

Appendix A contains four maps and one table that will help the reader identify facilities/areas discussed within this document. Figure A.1 is a comprehensive PGDP site map and site index. Figure A.2 is a Paducah Site map showing current solid waste management unit (SWMU) locations. Figure A.3 is a map depicting the 2016 Trichloroethene (TCE) groundwater plume. Figure A.4 is a map depicting the 2016 Technetium-99 (Tc-99) groundwater plume. Table A.1 is a SWMUs/areas of concern (AOCs) by operable unit (OU) cross-reference table. This table identifies each facility or AOC by OU, subproject, SWMU number, and gives a brief description of the facility. In addition, the table provides a list of SWMUs requiring no further action (NFA) and a list of Decontamination and Decommissioning OU facilities identifying current operational status.

2. PHYSICAL CHARACTERISTICS

The Paducah Site limited area is heavily industrialized; however, the area surrounding the plant is mostly agricultural and open land, with some forested areas. The West Kentucky Wildlife Management Area that borders the Paducah Site to the north, west, and south is an important recreational resource. Figures 1 and 2 illustrate the reasonably anticipated future land use and the current mixed industrial and recreational land use of the PGDP area, respectively. The geomorphology, geology, and hydrology of this facility and surrounding areas have undergone extensive study, review, and documentation. In-depth area descriptions may be found in numerous other DOE documents describing the DOE property at the Paducah Site.

2.1 GEOMORPHOLOGY

Located in the Jackson Purchase Region of western Kentucky, the Paducah Site lies within the northern tip of the Mississippi Embayment portion of the Gulf Coastal Plain Province (Clausen et al. 1992). The DOE property is characterized by mostly flat areas and low, gently sloped hills (< 50 ft of vertical relief). Drainage patterns are naturally dendritic, but have been modified to follow roads within the area surrounded by the PGDP security fence.

2.2 SITE GEOLOGY

The stratigraphic sequence in the region consists of Cretaceous, Tertiary, and Quaternary sediments overlying eroded Mississippian bedrock. Figure 3 shows a columnar section of the geology of the Jackson Purchase Region, and Figure 4 presents a schematic cross section that illustrates regional stratigraphic relationships near the Paducah Site.

Bedrock beneath the Paducah Site is comprised of Mississippian-age limestone. In the vicinity of the Paducah Site, the bedrock is directly overlain by interbedded and interlensing sand, silt, and clay of the Upper Cretaceous McNairy Formation. Data indicate that sand may account for 40 to 50 percent of the McNairy Formation at the Paducah Site. The Upper Cretaceous Tuscaloosa Formation, which directly overlies Paleozoic bedrock to the north, has not been encountered during drilling activities conducted at the Paducah Site.

The Paleocene Porters Creek Clay occurs in the southern portions of the site and consists of dark gray to black clay with varying amounts of silt and fine-grained micaceous, commonly glauconitic, sand. The Porters Creek Clay subcrops along a buried terrace slope that extends east-west across the site. Eocene sediments, consisting of interbedded and interlensing sand, silt, and clay, overlie the Porters Creek Clay in the extreme southern portion of the DOE Reservation.

Miocene, Pliocene, and Pleistocene continental deposits unconformably overlie Cretaceous through Eocene strata at the Paducah Site. The thicker sequence of Pleistocene continental deposits represents a valley fill that comprehensively comprises a thick, fining upward sequence. The continental deposits extend from the southern end of the plant to the Ohio River and overlay an unconformity that exhibits




Figure 1. Reasonably Anticipated Future Land Use at PGDP




Figure 2. Current Land Use at PGDP

SYSTEM	SERIES	FORMATION	THICKNESS (IN FT)	DESCRIPTION	HYDROGEOLOGIC SYSTEMS
×	RECENT_AND PLEISTOCENE	ALLUVIUM	0-40	Brown or gray sand and silty clay or clayey silt with streaks of sand.	
NAR	PLEISTOCENE	LOESS	0-43	Brown or yellowish-brown to tan unstratified silty clay	Upper Continental Recharge System
QUATERNARY	PLEISTOCENE	CONTINENTAL DEPOSITS	3-121	Upper Continental Deposits (Clay Facies)—mottled gray and yellowish brown to brown clayey silt and silty clay with some very fine sand. Trace of gravel. Often micaceous Lower Continental Deposits	(UCRS)
	PLIOCENE- MIOCENE (?)			(Gravel Facies)—reddish- brown clayey, silty, sandy chert, gravel, and beds of gray sand.	Regional Gravel Aquifer (RGA)
	EOCENE	JACKSON, CLAIBORNE, AND WILCOX FORMATIONS	0-200+	Red, brown, or white fine-to- coarse grained sand. Beds of white to dark gray clay are distributed at random.	
TERTIARY			0-100+	White to gray sandy clay, clay conglomerates and boulders, scattered clay lenses and lenses of coarse red sand. Black to dark gray lignitic clay, silt or fine-grained sand.	McNairy
	PALEOCENE	PORTERS CREEK CLAY	0-200	Dark gray, slightly to very micaceous clay. Fine-grained clayey sand, commonly glauconitic in the upper part. Glauconitic sand and clay at the base.	Flow System
		CLAYTON FORMATION	Undetermined	Lithologically similar to the underlying McNairy Formation.	
	UPPER TACEOUS	McNAIRY FORMATION	200-300	Grayish-white to dark gray micaceous clay, often silty, interbedded with light gray to yellowish-brown very fine-to- medium grained sand with lignite and pyrite. The upper part is interbedded clay and sand, and the lower part is sand.	
(Soliday)		TUSCALOOSA FORMATION	Undetermined	White, well rounded, or broken chert gravel with clay.	
MISSISSIPPIAN		MISSISSIPPIAN CARBONATES	500+	Dark gray limestone and interbedded chert with some shale.	

Adapted from USGS 1980

Figure 3. Lithostratigraphic Column of the Jackson Purchase Region*

*Historically, the geologic section used at the Paducah Site reflects the stratigraphy, as mapped by Wilds W. Olive in the United States Geological Survey publication, *Geologic Maps of the Jackson Purchase Region, Kentucky* (USGS 1980). This document was published in 1980 in cooperation with the Kentucky Geologic Society. At the Paducah Site, the probable age of the Terrace Gravel is considered to be of Miocene or Pliocene age.




Figure 4. Schematic of Stratigraphic and Structural Relationships near PGDP

steps, or terraces. These continental deposits have been divided into a basal gravel facies [Lower Continental Deposits (LCD)] and an upper, fine-grained clastic facies [Upper Continental Deposits (UCDs)].

The LCD consists of chert gravel in a matrix of poorly sorted sand and silt. This basal gravel facies has been identified at three horizons at the Paducah Site. A Miocene-to-Pliocene-aged facies, ranging in thickness from 1 to 30 ft and averaging less than 10 ft, exists in the southern portions of the site, occurring on the upper surfaces of a buried terrace at elevations greater than 350 ft above mean sea level (amsl). A second gravel facies, ranging in thickness from 15 to 20 ft, exists in southeastern and eastern portions of the site occurring on an erosional surface at approximately 320 to 345 ft amsl. The third and most prominent of the three gravel facies beneath the site consists of Pleistocene deposits that overlie an erosional surface north of the buried Porters Creek Clay Terrace. Elevations of this facies vary from approximately 245 to 310 ft amsl. Overall the LCD has an average thickness of approximately 30 ft, but thicker deposits, up to 70 ft, exist in deeper scour channels that trend east-west across the site.

The UCD is primarily a fine-grained, clastic facies varying in thickness from 15 to 55 ft and consisting of clayey silt with lenses of sand and occasional gravel. The UCD represents fluvial and lacustrine environments (Finch 1967; Frye et al. 1972). Lacustrine sediments were deposited along the present Ohio and Tennessee River Valleys when the Mississippi River Valley and ancestral Ohio River Valley became choked from draining glaciated areas. These sediments dammed valleys of tributaries, creating slackwater lakes, and resulting in deposition of fine-grained sediments. Depending on stages of glaciation, periods of lacustrine deposition were followed by periods of erosion. As aggradation of the fluvial system continued, stream gradients in the ancestral Tennessee River and tributaries lessened. Lower gradients likely favored a transition from a braided environment to a meandering environment. A very gravelly lower sequence that becomes sandier upward identifies the transition in the Pleistocene continental deposits.

Loess, consisting of yellowish-brown silt and clayey silt, overlies the continental deposits at the site, and varies in thickness from approximately 5 to 25 ft with an average of approximately 15 ft. Holocene alluvial deposits are found at lower elevations within the Ohio River floodplain north of the plant site.

The general soil map for Ballard and McCracken counties indicates three soil associations are found in the vicinity of the Paducah Site (USDA 1976): the Rosebloom-Wheeling-Dubbs association, the Grenada-Calloway association, and the Calloway-Henry association. The predominant soil association in the vicinity of the Paducah Site is the Calloway-Henry association, which consists of nearly level, somewhat poorly drained to poorly drained, medium-textured soils on upland positions. Many of the characteristics of the original soil have been lost due to industrial activity that has occurred over the past 67 years.

2.3 SITE HYDROLOGY

Local groundwater near the Paducah Site occurs in the unconsolidated sediments of the Cretaceous McNairy Formation, Miocene-Pliocene Terrace Gravel, and Pleistocene LCD and UCD. Terms describing the hydrogeologic-flow systems that generally correspond to these lithostratigraphic units are the McNairy Flow System, Terrace Gravel, Regional Gravel Aquifer (RGA), and Upper Continental Recharge System (UCRS). The following are brief descriptions of the four components of the groundwater flow system:

(1) **McNairy Flow System:** Formerly termed "the deep groundwater system," this component consists of the interbedded and interlensing sand, silt, and clay of the McNairy Formation. Sand facies account for 40 to 50 percent of the total formation thickness of approximately 225 ft.

- (2) **Terrace Gravel:** This component consists of Miocene-to-Pliocene-aged gravel deposits found at elevations higher than 350 ft amsl in the southern portion of the plant site. These deposits usually lack sufficient thickness and saturation to constitute an aquifer and typically are characterized by an unsorted mix of sand to cobble-sized materials.
- (3) **RGA:** This component consists of the Pleistocene sand and gravel facies of the LCD and Holocene alluvium found adjacent to the Ohio River. In addition, the RGA includes contiguous sands of the UCD and the McNairy Formation. The RGA is commonly thicker than the Pliocene gravel deposits, with an average thickness of 30 ft, and ranges up to 70 ft in thickness along an axis that trends east to west through the plant site. The RGA, which extends well beyond the site boundary, is the primary aquifer used locally and serves as the main conduit for groundwater flow to the north where it discharges to the Ohio River. Some of the RGA groundwater discharges in springs/boils in tributaries to the Ohio River.
- (4) **UCRS:** Formerly termed "the shallow groundwater system," this component consists of the UCD, excluding sand adjacent to the LCD. The sand and gravel lithofacies are relatively discontinuous. The most prevalent sand and gravel deposits occur at an elevation of approximately 345 to 351 ft amsl, with less prevalent deposits occurring at an elevation of 337 to 341 ft amsl. Groundwater flows downward into the RGA from the UCRS in the vicinity of the Paducah Site.

The local groundwater flow system at the Paducah Site is bound by topographically controlled recharge and discharge areas to the south and north, respectively. Recharge within the Pliocene Terrace Gravel and Eocene sands has resulted in a groundwater divide located southwest of the Paducah Site. Locally, groundwater within the Terrace Gravel and Eocene sands either discharges to streams or flows northward into the RGA, which eventually discharges to the Ohio River, the regional base level for the system. The main recharge for the RGA is through flow from the UCRS.

Toward the southern part of the Paducah Site, the RGA either is truncated or thins and grades laterally into the Terrace Gravel; high hydraulic potential causes groundwater to discharge into adjoining streams. In the north-central portion of the plant site, the lower gradients are a result of the thicker LCD. The hydraulic gradient increases closer to the Ohio River as a result of a thinner section of the RGA or the low permeability of bottom sediments in the Ohio River. The primary pathway of groundwater flow at the Paducah Site is within the RGA, which dominates the flow regime.

The discontinuous nature of sands and gravels in the UCRS and the large vertical gradient within the UCRS require groundwater flow in the UCRS to be oriented predominantly downward into the RGA. Some horizontal flow in the UCRS likely occurs; however, it is insignificant near the Paducah Site due to the lateral discontinuity of shallow sand and gravel lenses. Groundwater flow in the RGA is to the north and discharges into the Ohio River and into Little Bayou Creek in the vicinity of the Tennessee Valley Authority plant. Hydraulic conductivities of the RGA range from 100 to 1,000 ft per day. Existing regional maps and borehole logs indicate the RGA is thin or absent beneath the Ohio River, suggesting that flow under the Ohio River is unlikely.

THIS PAGE INTENTIONALLY LEFT BLANK

3. ACTIVITIES THAT HAVE THE POTENTIAL TO POLLUTE GROUNDWATER

Activities for which groundwater protection plans shall be prepared and implemented are listed in 401 *KAR* 5:037 § 2(2). The following activities, relevant to these requirements, are performed by DOE and its contractors/subcontractors at the Paducah Site:

- (a) *Storing or related handling of bulk quantities of pesticides or fertilizers for commercial purposes.* This primarily is performed by the Infrastructure Contractor. Examples include the following:
 - Storage of concentrated herbicides is in a secure, weatherproof "clamshell" structure north of C-755-A and at C-725. Only personnel with current state certifications for herbicide application are allowed to access the chemicals, mix, and apply the chemicals.
 - Fertilizers are used by the D&R Contractor to aid in sowing down landfill vegetation. Fertilizers are stored in a Poly-Overpack[®], which is stored inside a wooden storage facility (C-746-U-11).
 - The Infrastructure Contractor uses spike type fertilizers for targeted application to trees and ornamentals; spikes are stored at C-755-T27.
- (b) *Storing or related handling of bulk quantities of pesticides or fertilizers for the purpose of distribution to a retail sales outlet.* (Not Applicable)
- (c) *Applying of pesticides or fertilizers for commercial purposes.* (Not Applicable)
- (d) *Applying of fertilizers or pesticides for public right-of-way maintenance or institutional lawn care.* This primarily is performed by the Infrastructure Contractor.
- (e) *Land treatment or land disposal of a pollutant*. (Not Applicable)
- (f) Storing, treating, disposing, or related handling of hazardous waste, solid waste, or special waste in landfills, incinerators, surface impoundments, tanks, drums or other containers, or in piles. This primarily is performed by the D&R Contractor.
 - C-733, C-746-Q, and C-752-A are permitted hazardous waste storage and treatment units in accordance with the Hazardous Waste Facility Permit, KY8-890-008-982, issued by Kentucky Division of Waste Management (KDWM).
 - C-746-U receives and disposes of solid wastes in accordance with Solid Waste Permit SW07300015, SW07300014, SW07300045 issued by KDWM. The C-746-U Landfill also has six large capacity storage tanks (two 31,000-gal, two 13,100-gal, one 16,000-gal, and one 2,500-gal) to facilitate the collection and treatment of leachate generated at the landfill and also from the C-746-S Landfill.
 - C-404 Landfill is a closed landfill listed on the Hazardous Waste Facility Permit, KY8-890-008-982.
 - C-746-S and C-746-T are Subtitle D RCRA-closed landfills listed on the Solid Waste Permit SW07300014, SW07300015, SW07300045.

- Various projects/facilities are used for the temporary staging/storage of hazardous/solid waste per applicable regulations. These areas may include Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) waste staging areas managed in accordance with an approved CERCLA decision document.
- Solid wastes are staged in covered roll-offs, trucks, and/or intermodals prior to transfer to the C-746-U Landfill for disposal to prevent accumulation of precipitation or condensation in the waste containers. Receipt/processing of waste at the landfill is performed in accordance with the solid waste landfill permit, which prohibits receipt of free liquids in the waste. Waste is disposed of within 2 hours of receipt at the landfill and covered with daily cover by the end of each day. Interim and long-term covers are used at areas of the landfill that are not used for extended periods, per the permit, to minimize infiltration of water into the waste.
- Twenty-two intermodal containers in C-746-Q are holding uranium compounds pending disposition and disposal as waste.
- (g) Commercial or industrial storing or related handling in bulk quantities of raw materials, intermediate substances or products, finished products, substances held for recycling, or other pollutants held in tanks, drums or other containers, or in piles. This is performed by each contractor in differing amounts and purposes.

The Spill Prevention, Control, and Countermeasure Plan for the U.S. Department of Energy Paducah Site, McCracken County, Kentucky, PAD-REG-1005, (SPCC) identifies the petroleum-based materials stored on-site (FRNP 2018a). Select examples of bulk storage sites are discussed below.

- A 1,000-gal stationary tank used to store diesel fuel for heavy equipment and a 500-gal stationary tank that stores gasoline for vehicles are located at the C-746-U Landfill.
- Two 420,000-gal tanks (C-601-A and C-601-B) are located at the facility. Both tanks are located within a 675,000-gal capacity containment structure consisting of an earthen dike lined with a synthetic material impervious to oil.
- C-601-A currently is empty and no longer is used for oil storage, but serves as emergency containment for the C-601-B tank in the event of a leak.
- C-601-B tank is used to charge a 500-gal day tank, which is used to store fuel oil for backup operations associated with two of the five newly-installed, portable steam generator units.
- A historical bulk coal storage area exists near the "out of service" C-600 Steam Plant. The bulk of the coal has been removed (facility currently is out of service).
- A 150-gal tank containing used oil is at C-755-Y.
- Six 10,000-gal aboveground, polymer-lined, carbon steel bulk storage tanks outside the DUF₆ Conversion Building (tanks C-0-HFS-550 to 555) are for the storage of aqueous hydrogen fluoride (HF).
- DUF₆ is stored in the site's cylinder storage yards east of the DUF₆ Conversion Plant in approximately 36,000 steel cylinders.

- UF₆ is stored in facilities and cylinders located in the site's cylinder storage yards and processing facilities (e.g., C-310, C-315, C-331, C-333, C-335, C-337, and C-360).
- Posi-Shell[®] is a clay and polymer-based alternative daily cover material that is stored in metal Sealand containers at the C-746-U Landfill.
- Flocculants are used for the treatment of suspended solids in the sedimentation pond and are stored in a metal Sealand container at the C-746-U Landfill.
- (h) Transmission in pipelines of raw materials, intermediate substances or products, finished products, or other pollutants. This is performed by each contractor in different amounts and for different purposes. Examples include the following:
 - UF₆ piping between process buildings
 - C-600 No. 2 fuel oil piping
 - Transformer oil piping
 - Piping for C-611, C-616, C-752-B aboveground storage tanks
 - Piping associated with C-765 and C-765-A Northeast Plume Treatment systems
 - Piping associated with C-612 Northwest Plume Treatment system
 - Piping associated with former C-614 Northeast Plume Treatment system (maintained in standby status)
- (i) *Installation or operation of on-site sewage disposal systems*. This is performed by the D&R Contractor. Examples include the following:
 - C-615 Sewage Treatment Plant
 - C-333-A and C-337-A Extended Aeration Systems
 - C-611, C-612, and C-746-A Septic Systems
- (j) *Storing or related handling of road oils, dust suppressants, or deicing agents at a central location.* This primarily is performed by the infrastructure contractor.
 - Road deicer is stored at the C-732 storage building and in two locations in C-755 Area: C-755-U and C-755-V. Each structure is an approximately 20 ft tall, covered metal storage buildings with an open front for loading/unloading. The floor at C-732 storage building is concrete to minimize moisture intrusion and loss of salt material to the environment. The C-755-U and C-755-V storage facilities have rubber, barrier-pad covers on gravel surface to minimize moisture intrusion and loss of salt material into the environment.
- (k) Application or related handling of road oils, dust suppressants or deicing materials. This primarily is performed by the infrastructure contractor, although each of the contractors applies small amounts of deicing materials around facility entryways/walkways for safety when needed. This activity typically is performed around each facility.
- (1) *Mining and associated activities*. (Not Applicable)

- (m) Installation, construction, operation, or abandonment of wells, bore holes, or core holes. The Paducah Site was placed on the National Priorities List in 1994. As a result, wells and bore holes are installed in accordance with CERCLA and as such would be exempt from administrative requirements in this plan. Rather, they are conducted in accordance with the substantive requirements of an approved CERCLA decision document. Wells installed under other programs (e.g., hazardous waste landfill, solid waste landfill) would be completed in accordance with this plan and applicable permits and subsequent regulations under 401 KAR.
- (n) Collection or disposal of pollutants in an industrial or commercial facility through the use of floor drains which are not connected to on-site sewage disposal systems, closed-loop collection or recovery systems, or a waste treatment system permitted under the Kentucky Pollutant Discharge Elimination System.

Liquids from plant operations are discharged through plant effluent ditches. Groundwater protection from effluents in these discharges is under the purview of the Kentucky Pollutant Discharge Elimination System (KPDES); therefore, it is not addressed further in this GPP. Compliance with the KPDES program ensures protection of the groundwater from plant effluent discharges.

- (o) Impoundment or containment of pollutants in surface impoundments, lagoons, pits, or ditches. This is performed by the D&R Contractor and the DUF₆ Conversion Project contractor. Examples include these:
 - C-611-V, C-611-Y, C-611-H, and C-611-U are containment basins used for the backwash from the treatment of Ohio River water for potable uses on-site.
 - C-616 is a series of settling basins constructed to hold recirculating cooling water for phosphate reduction prior to discharge.
 - C-617 lagoons collect storm water and various industrial wastewaters. Sodium thiosulfate and carbon dioxide are fed into the lagoon to dechlorinate the effluent and control pH before discharge.
 - Fifteen outfall ditches convey storm water and treated industrial waste waters off-site in accordance with the KPDES permit. Each of these ditches contains devices with the potential to impound or contain wastewaters during transport off-site (e.g., inverted pipe dams, culverts).
 - C-745-G1 is a large concrete basin to collect storm water runoff from the C-746-G Cylinder Yard prior to lifting runoff to Outfall 017.
- (p) Commercial or industrial transfer, including loading and unloading, in bulk quantities of raw materials, intermediate substances or products, finished products, substances held for recycling, or other pollutants. This is performed by each contractor in differing amounts and for different purposes. Examples include the following.
 - C-760, C-759, rail lines, and the staging/receiving area along Hobbs Road (C-761-A) are used to stage wastes being shipped off-site for treatment and/or disposal.
 - C-720 Shipping and Receiving Area is used to stage incoming bulk materials for use at the site.
 - Aqueous HF is pumped from the storage tanks (tanks C-0-HFS-TK-550 to 555) into a railcar or tank truck for off-site shipment.

- Historically, C-333-A Autoclave Feed Facility, C-337-A Autoclave Feed Facility, C-360 Transfer and Sampling Facility, C-310 Product Removal Facility, and C-315 Tails Removal Facility were used to transfer UF₆ from process lines/equipment to cylinders; however, this facility currently is out of service.
- Used oil is pumped directly from the 150-gal tank at C-755-Y for off-site shipment.

Additionally, 401 KAR 5:037 § 2(4) lists several activities that are excluded from the provisions of this administrative regulation.

- (a) *Normal use or consumption of products sized and packaged for personal use by individuals.* This is performed by each contractor in differing amounts and for different purposes.
- (b) *Retail marketing of products sized and packaged for personal use or consumption by individuals.* (Not Applicable)
- (c) Activities that are conducted entirely inside enclosed buildings. Several facilities used by contractors/subcontractors qualify for this exclusion; these uses include, but are not limited to, employee training, business conferences, meetings, and general office work.
- (d) *Storing, related handling, or transmission in pipelines of pollutants that are gases at standard temperature and pressure.* This exclusion applies to the storage and transfer of gases in cylinders and process piping, such as fluorine, chlorine, Freon[™], and chlorine trifluoride.
- (e) Storing municipal solid waste in a container located on property where the municipal solid waste is generated and which is used solely for the purpose of collection and temporary storage of that municipal solid waste prior to off-site disposal. This is performed by each contractor in differing amounts throughout the facility.
- (f) *Installing and operating sewer lines or water lines approved by the cabinet*. This exclusion applies to the septic water lines that run from the process and operating buildings to the on-site sewage treatment plant.
- (g) *Storing water in ponds, lakes, or reservoirs.* This exclusion applies to Ohio River water storage at the C-611 Water Treatment Plant.
- (h) *Impounding stormwater, silt, or sediment in surface impoundments.* Several facilities used by contractors/subcontractors qualify for this exclusion, including the DUF₆ detention basin, C-613 basin, C-617 basin, etc.
- (i) Application of chloride-based deicing materials used on roads or parking lots. This primarily is performed by the infrastructure contractor, although each of the contractors will keep small amounts of deicing materials near facility entryways/walkways for use in clearing ice on walkways.
- (j) *Emergency response activities conducted in accordance with local, state, and federal law.* These are performed by each contractor in differing amounts and for different purposes.
- (k) Fire fighting activities. This will be performed by contractors/subcontractors.
- (1) *Conveyance or related handling by motor vehicle, rolling stock, vessel, or aircraft.* These are performed by each contractor in differing amounts and for different purposes.

- (m) Agricultural activities at agriculture operations. (Not Applicable)
- (n) Application by commercial applicators of fertilizers or pesticides on lands used for agriculture operations. (Not Applicable)

Operations at the Paducah Site are conducted in numerous facilities and areas across the Paducah Site. Contractors/subcontractors control these facilities and areas to ensure established waste management practices that result in groundwater protection practices are in place and properly functioning.

4. PRACTICES SELECTED TO PROTECT GROUNDWATER FROM POLLUTION

DOE uses contractors at the Paducah Site under the Environmental Management (EM) cleanup mission. The D&R Contractor is responsible for the deactivation of the uranium enrichment facilities and the implementation of environmental restoration activities (cleanup and closure of facilities and cleanup of soil, groundwater, burial grounds, and disposal of legacy waste) at the Paducah Site. The Infrastructure Contractor is responsible for infrastructure services such as surveillance and maintenance of selected facilities, property and records management, janitorial services, and grounds and roadway maintenance. The DUF₆ Contractor is responsible for the operation of a DUF₆ Conversion Plant. To ensure groundwater at the Paducah Site is protected from site-based pollution, DOE, and their contractors use standardized plans and procedures to assure quality and consistency in the implementation of groundwater protection practices. The following general programs at the Paducah Site are maintained by DOE contractors:

- Environment, Safety, and Health
- Integrated Safety and Environmental Management Systems
- Spill Prevention, Control, and Countermeasure Plan
- Best Management Practices Plan (BMP)
- Emergency Response Action Plan
- Facility Response Plan
- Uranium Programs
- Waste Management
- Transportation
- Radiological Controls
- Environmental Monitoring
- Data and Sampling
- Well Maintenance
- D&R

A list of relevant plans and procedures are in Appendix B.

The following sections provide brief descriptions of the groundwater protection practices that have been implemented at the Paducah Site.

4.1 INTEGRATED SAFETY MANAGEMENT SYSTEM AND ENVIRONMENTAL MANAGEMENT SYSTEMS

The Paducah Site is committed to performing work safely and ensuring the protection of its workforce, the public and the environment. In order to meet these goals DOE has embraced the Integrated Safety Management System (ISMS) and expects its contractor/subcontractor to adhere to the five Safety Management core functions and the eight guiding principles of ISMS. In addition, DOE sites must use Environmental Management System (EMS) as a platform for Site Sustainability Plan implementation and programs with objectives and measurable targets that contribute to DOE's meeting its sustainability goals. EMS enables more effective use of natural resources, provides better protection of the environment, and achieves environmental sustainability. The EMS helps to insure consistency and rigor in existing environmental activities and drives continual improvements in environmental performance. In addition to

ISMS/EMS, several other environmental based programs have been established to help foster and ensure environmental due diligence.

The Environmental Monitoring Plan (EMP) is intended to document the rationale, sampling frequency, parameters, and analytical methods for EM activities at the Paducah Site and provide information on site characteristics, environmental methodologies, and quality assurance managemental pathways, dose assessment methodologies, and quality assurance management (FRNP 2018b). EM at the Paducah Site consists of effluent monitoring and environmental surveillance activities and supports evaluation and assessment if an unplanned release occurs. Monitoring is conducted for a variety of media, including air, surface water, groundwater, and sediment.

The Best Management Practices Plan, Paducah Gaseous Diffusion Plant, Paducah, Kentucky, PAD-REG-1006, (FRNP 2018c) is required per Section 3 of Kentucky Pollutant Discharge Elimination System Permit for the Paducah Site. The plan is required for "all permittees who use, manufacture, store, handle, or discharge any pollutant listed as: (1) toxic under Section 307(a)(1) of the Clean Water Act; (2) oil, as defined in Section 311(a)(1) of the Act; (3) any pollutant listed as hazardous under Section 311 of the Act; or (4) is defined as a pollutant pursuant to KRS 224.1-010(35) and who have operations which could result in (1) the release of a hazardous substance, pollutant, or contaminant, or (2) an environmental emergency, as defined in KRS 224.1-400, as amended, or any regulation promulgated pursuant thereto (hereinafter, the 'BMP pollutants'). These operations include material storage areas; plant site runoff; in-plant transfer, process and material handling areas; loading and unloading operations, and sludge and waste disposal areas."

The BMP must be maintained consistent with 401 *KAR* 5:065 § 2(4) pursuant to *KRS* 224.70-110, which prevents or minimizes the potential for the release of "BMP pollutants" from ancillary activities through site runoff; spillage or leaks, sludge or waste disposal; or drainage from raw material storage at the Paducah Site. The BMP has general requirements for all operations and specific requirements for individual operations. The plan discusses a required BMP committee, the reporting of BMP incidents, and risk identification and assessment. The plan also discusses employee training, inspection records, preventative maintenance, housekeeping requirements, materials inventory, and security.

4.2 GROUNDWATER MONITORING

To ensure groundwater at the Paducah Site is protected from site-based pollution, DOE and their contractors integrate principals from the ISMS/EMS, the EMP, and BMP plans into the overall groundwater strategy.

4.2.1 RCRA Subtitle C Monitoring

Currently, the only RCRA Subtitle C permitted facility at the Paducah Site that requires groundwater monitoring is the C-404 Low-Level Radioactive Waste Burial Ground. The C-404 unit was used as a low-level waste lagoon/burial ground from the early 1950s until 1986. At that time, routine testing determined that, of the wastes disposed of there, gold-dissolver precipitate was considered a hazardous waste under RCRA. The landfill was covered with a RCRA-compliant clay cap (final cover) and was certified "closed" in 1991 as a hazardous waste landfill. The postclosure permit for this facility was incorporated into the Hazardous Waste Management Permit, KY8-890-008-982, in 1992.

Monitoring wells (MWs) were installed to monitor groundwater quality during the postclosure care period. The MWs were installed in the UCRS and the underlying RGA, which is considered to be the uppermost regulatory aquifer. A statistical evaluation of the indicator parameters was conducted using

quarterly sample results from the initial year of monitoring. As a result, the Commonwealth of Kentucky determined that additional information was needed to support the postclosure permit application, and subsequent MWs were installed to provide upgradient monitoring of the Lower RGA and the Upper RGA (refer to Appendix B to the EMP).

The MW network at C-404 is sampled and monitored in accordance with the requirements associated with the Hazardous Waste Facility Permit (KY8-890-008-982). The data resulting from sampling is statistically analyzed to determine if the landfill is impacting the groundwater. This analysis is supplied in semiannual reports to KDEP.

4.2.2 Underground Storage Tank Monitoring

Hazardous and Solid Waste Amendments under Subtitle I of RCRA regulation (40 *CFR* Part 280), established a comprehensive regulatory program for underground storage tanks (USTs). The Subtitle I regulations generally pertain to all USTs used to store "regulated substances." Regulated substance means (a) any substance defined in section 101(14) of CERCLA (but not including any substance regulated as a hazardous waste under subtitle C); and (b) petroleum, including crude oil or any fraction thereof that is liquid at standard conditions of temperature and pressure (60°F and 14.7 pounds per square inch absolute). The term "regulated substance" includes, but is not limited to, petroleum and petroleum-based substances comprised of a complex blend of hydrocarbons derived from crude oil though processes of separation, conversion, upgrading, and finishing, such as motor fuels, jet fuels, distillate fuel oils, residual fuel oils, lubricants, petroleum solvents, and used oils. RCRA-regulated wastes are specifically exempt from the Subtitle I (UST) regulations, and releases from USTs that contain RCRA wastes are addressed under the regulations governing corrective action. In addition to these federal regulations, USTs at the Paducah Site also are subject to 401 *KAR* Chapter 42.

DOE is responsible for 18 site USTs that have been reported to KDEP in accordance with regulatory notification requirements. All 18 of these USTs and associated piping runs have been closed in place permanently or physically removed and properly disposed of in accordance with KDEP regulations and KDEP NFA letters are on file for each former UST facility. Table 1 provides summary information on the former USTs at the Paducah Site. Visit the following webpage for additional information: https://pegasis.ffspaducah.com/.

4.2.3 RCRA 3004 (u/v) and CERCLA Monitoring

Additional groundwater monitoring performed relates to RCRA 3004 (u/v) and CERCLA requirements for characterization of areas of contamination at a facility that has had releases with the potential to contaminate groundwater. Groundwater contamination currently present at the Paducah Site has been labeled as the TCE Plume and the Tc-99 Plume (see Figures A.3 and A.4). The TCE Plume is subdivided further into the Northeast Plume, Northwest Plume, and Southwest Plume. Results of monitoring are used to determine and implement remedial actions, as necessary, to protect human health and the environment. Specific actions/procedures to protect groundwater during MW installation and groundwater remediation are identified in the CERCLA response work plans. Annual, semiannual, and quarterly analytical data collected in conjunction with groundwater monitoring sampling events are posted to the Environmental Information System PEGASIS data repository.

Table 1.	Summary	Information	on USTs
----------	---------	-------------	---------

State Identification Number	PGDP Identification Number	SWMU Designation/ Status	Regulatory Status
0001	C-750-A	142	Removed 3/91; closure complete per KDWM letter of 3/25/99.
0002	С-750-В	143	Removed 3/91; closure complete per KDWM letter of 3/25/99.
0003	С-750-С	25	Removed 10/93; not Subtitle I—clean closed under RCRA Subtitle C.
0004	C-750-D	24	Rinsed with TCE and emptied 6/79; filled with cement 10/97; closure complete per KDWM letter of 11/23/99.
0005	C-746-A1	139	Emptied 9/88; filled with cement 10/97; revised closure assessment report submitted 07/15/03; additional information requested from KDWM on 03/18/04; closure complete per KDWM letter.
0006	С-710-В	73	EXEMPT—emptied 7/85; filled with cement 10/97; closure complete per KDWM letter of 02/19/02.
0007	C-200-A	72	EXEMPT—grouted in 1977; closure complete per KDWM letter of 11/23/99.
0008	C-746-A2	140	During the Waste Area Group 15 Site Investigation, this UST was determined (and documented) to be nonexistent.
0009	C-751-W	186	Removed 2/27/2015: closure complete per KDWM NFA letter dated 10/21/2015.
0010	С-751-Е	186	Removed 2/27/2015: closure complete per KDWM NFA letter dated 10/21/2015.
0011	C-611-1	130	Last used before 1975; clean closed per KDWM letter of 12/6/96.
0012	C-611-3	134	Last used before 1975; filled with cement 9/97; clean closed per KDWM letter of 12/6/96.
0013	C-611-2	131	This UST was determined to be nonexistent—NFA required per state correspondence of 12/6/96.
0014	C-611-4	132	Last used before 1975; filled with sand; clean closed per KDWM letter of 12/6/96.
0015	C-611-5	133	Filled with grout before 1975; clean closed per KDWM letter of 12/6/96.
0016	С-200-В	72	Filled with concrete around 1981; closure complete per KDWM letter of 02/19/02.
0017	С-745-К	490	UST discovered 08/16/01; tank and soils removed 02/02, clean closed per KDWM letter of 12/4/02.
0018	C-745-K2	534	UST discovered 04/10/02; tank removed 04/02; clean closed per KDWM letter of 12/4/02.

4.2.4 RCRA Subtitle D Landfill Groundwater Monitoring

Both C-746-S and C-746-T Landfills are closed landfills in postclosure care under the Solid Waste Permit (SW07300014, SW07300015, SW07300045) issued by KDWM on September 28, 2017. The C-746-S Residential Landfill stopped receiving solid waste and was certified "closed" in 1995. The groundwater monitoring system for the C-746-S Residential Landfill also encompasses the C-746-T Inert Landfill, which was certified "closed" in 1992.

A solid waste landfill, C-746-U, was constructed in 1996 north of C-746-S and C-746-T Landfills. The C-746-U Landfill currently operates and receives wastes as a contained landfill under Solid Waste Permit (SW07300014, SW07300015, SW07300045). MWs for the C-746-S, C-746-T, and C-746-U Landfills are sampled quarterly for analytes dictated by the current, approved Solid Waste Permit.

The data resulting from groundwater sampling at C-746-U and C-746-S&T Landfills are statistically analyzed to determine if the landfills are impacting the groundwater. This analysis is supplied in quarterly reports to KDEP.

4.2.5 Monitoring Well Preventive Maintenance

To protect and maintain the integrity of the MW network at the Paducah Site, a preventive monitoring well maintenance plan was implemented in 2002. A complete description of this program can be found in the current approved CP2-ES-0024, *Monitoring Well Maintenance Implementation Plan for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky.* This program combines regular monitoring of each well's physical condition and performance during routine sampling activities. If problems requiring attention are identified, a schedule to repair or rehabilitate wells is developed. The maintenance monitoring program also includes, as needed, visual inspection of downhole equipment, downhole video inspection, evaluation of water quality data, microbial sampling and analysis, and assessment of well performance indicators. Typical efforts to rehabilitate MWs involve the use of physical treatment methods, such as brushing and surging.

4.2.6 Evaluation of Floor Drains

An evaluation of floor drains before groundwater protection practices are selected is required by 401 KAR 5:037 3(5)(c). Floor drains must be connected to an on-site sewage disposal system, to a closed-loop collection or recovery system, a waste treatment system permitted under KPDES, or be terminated.

Liquid discharges from plant operations are discharged through the plant effluent ditches, and groundwater protection from effluents in these discharges are under purview of the KPDES program and, therefore, are not addressed further in this GPP. Compliance with the KPDES program provides protection of the groundwater from plant effluent discharges.

4.2.7 Evaluation of Loading and Unloading Areas

401 *KAR* 5:037 § 3(5)(a) states:

Loading and unloading areas shall have spill prevention and control procedures and operation procedures designed to prevent groundwater pollution. Spill containment and cleanup equipment shall be readily accessible.

Loading and unloading areas have emergency response procedures, spill containment, and cleanup equipment. The plant emergency squad provides continuous emergency response to spills, 24 hours per day.

4.3 ENVIRONMENTAL SURVEILLANCE MONITORING

Groundwater surveillance monitoring, as required by DOE Order 436.1, *Departmental Sustainability*, is implemented at the Paducah Site. The approved EMP discusses this program and its components including MWs, sample parameters, and sampling frequencies. The plan is maintained as a living document that will be modified to meet new requirements and needs. Any changes in MW status, locations, or sampling frequency will be documented in the annual EMP. The EMP also describes other environmental monitoring activities, such as surface water monitoring at the C-746-S/T/U Landfills, KPDES outfall monitoring, and in-stream monitoring of Bayou and Little Bayou Creeks.

4.4 KENTUCKY POLLUTANT DISCHARGE ELIMINATION SYSTEM OUTFALLS

The KPDES permit (KY0004049) requires the Paducah Site to monitor effluent discharges through permitted Outfalls 001, 002, 004, 006, 008, 009, 010, 011, 012, 013, 015, 016, 017, 019, and 020 (Figure 5).

Sample parameters include both physical and chemical constituents. Results are assessed and submitted to the proper regulatory agencies. Activities include field testing (pH, conductivity, and temperature), field measurements (flow measurements), and laboratory analysis for pollutants identified in the KPDES permit. If data indicate increasing contaminant levels, information pertaining to upstream operations is reviewed to identify the potential cause and implement appropriate best management practices to minimize pollutants per Section 3 of the KPDES permit. General conditions and general requirements of Section 3 of the KPDES Permit are discussed in the FRNP BMP as they pertain to the remediation, deactivation, and infrastructure contractors and in *Paducah Storm Water Pollution Prevention and Best Management Practices Plan*, DUF6-PLN-079, (MCS 2017) for the DUF₆ Conversion Project contractor.

4.5 SAMPLE COLLECTION

Surface water bodies (streams, the Ohio River, lagoons, and ponds), surface and subsurface soil, and groundwater (from MWs) are sampled as part of environmental assessment and possible remediation efforts conducted at the Paducah Site. To provide protection of groundwater during the performance of these activities, task-specific procedures are utilized that allow quantification of site conditions without degradation of the sampling site. These procedures, maintained and implemented by DOE contractors, are specified and described in project-specific sampling and analysis plans that are reviewed and approved prior to sampling. In addition, the procedures utilized during sample-collection tasks are documented in the associated investigation or evaluation report published following completion of the assessment. The following sections in this report provide generic information on the types of procedures that are applicable to sampling surface water, surface and subsurface soil, and groundwater at the Paducah Site.

Appendix B provides a partial list of the most current version of procedures that are implemented for specific tasks at the Paducah Site.

4.5.1 Surface Water [401 KAR 5:037 § 2(2)(0)]

Surface water sampling activities can be divided into two types: observation and water sampling. Observations include presampling visual assessment and determination of flow rates or volumes using flow meters and calibrated flumes. The sampling protocol is designed to allow representative samples to be taken from a location and protect sampling personnel, while preventing the spread of contamination. Collected samples then are tested for specific constituents using either field measurement methods or laboratory analysis. Hydrogeologic evidence has demonstrated that Bayou Creek and Little Bayou Creek are losing streams over some intervals; therefore, sampling and protecting surface water aid in ensuring groundwater protection.




Figure 5. KPDES Outfall Locations at PGDP

Several SWMUs at the Paducah Site are located in areas without an outfall and are grass covered and under normal conditions would not have discharges. The BMP states that during extreme rainfall events these areas may become saturated, which may allow storm water to flow over or through the SWMU increasing the potential for surface water discharge. If the soils covering the SWMU become saturated, the SWMUs will be checked for signs of erosion and releases. Storm water runoff periodically will be inspected visually to look for signs of contamination (e.g., an oily sheen, cloudy or discolored water, etc.) and, if necessary, sampled.

The following types of activities are used during surface water sampling as appropriate to the specific task:

- Collection of surface water samples
- Field measurement of water temperature
- Field measurement of pH
- Field measurement of dissolved oxygen
- Field measurement of residual chlorine
- Field measurement of specific conductance
- Field measurement of alkalinity

4.5.2 Surface and Subsurface Soil [401 KAR 5:037 § 2(2)(m)]

Surface and subsurface soil samples may be taken prior to or during construction, excavation, and remediation activities or as part of environmental characterization activities. Procedures for soil sampling enable characterization while protecting sampling personnel and reducing the risk of increasing contaminant migration and are identified in project specific work instructions and/or CERCLA work plans.

The following activities may be used during surface and subsurface soil sampling as appropriate to the requirement of the specific task:

- Surface soil sampling
- Subsurface soil sampling
- Soil gas sampling
- Lithologic logging

4.5.3 Well Sampling [401 KAR 5:037 § 2(2)(m)]

Numerous MWs and residential wells are sampled on a regular basis (Appendix B of the EMP). This sampling is conducted to monitor the existing groundwater contamination plumes and to detect any additional releases of contamination into the RGA. The procedures that guide these activities help ensure that analytical results are representative of aquifer conditions. In addition to chemical and physical conditions, aquifer parameters such as transmissivity and conductivity are determined as needed. Additional information on the well sampling program at the Paducah Site is available in the current approved EMP.

The following types of activities may be used during well sampling, as appropriate to the specific task:

- Groundwater sampling
- Water level measurements
- Monitoring well purging

4.6 SUBSURFACE PENETRATIONS [401 KAR 5:037 § 2(2)(m)]

To characterize subsurface conditions, numerous subsoil penetrations have been made under various investigation and remedial activities. These penetrations have been in the form of MWs, production/extraction wells, piezometers, and sample borings (including shallow direct push holes and drilled borings to the McNairy Formation and deeper). Installation/drilling techniques are selected specifically to prevent undesirable alteration of contaminant migration while providing the maximum information required for characterization of the geological and hydrogeological conditions. Excavation permits are required by facility procedures [CP3-EN-0227 *Trenching, Excavation and Penetration Permit* (FRNP 2017)] prior to any installation/drilling activity anywhere on-site in order to satisfy ISMS/EMS principles. Completed sample borings and MWs no longer required for sampling are properly abandoned per 401 *KAR* 6:350 § 11 (as appropriate) to prevent downward migration of contaminants.

4.7 STORAGE OF BULK QUANTITIES OF MATERIALS, RECYCLABLES, AND WASTES [401 KAR 5:037 § 2(2)(a), (g), & (j)]

4.7.1 Fuel Storage Tanks

Fuel storage tanks located at the Paducah Site, including C-600, C-746-U, and C-752-B, are subject to the SPCC Plan. Each of the tanks is equipped with appropriate containment (secondary or double-walled) and is inspected at least monthly. Collected storm water is inspected for sheen prior to discharge. For a comprehensive overview of the Paducah Site aboveground storage tanks, refer to Appendix A to the SPCC Plan (FRNP 2018a). Additionally, spill control and cleanup equipment is located near each facility to allow for prompt cleanup of spills.

4.7.2 Used Oil

Used oil is collected for recycle in a 150-gal tank at C-755-Y. This tank is single-wall tank, but located within secondary containment. This tank is inspected every other week for evidence of leaks/drips. Once the waste oil tank is full, the infrastructure contractor schedules pick up of the used oil. Generally, a tanker truck is used for off-site shipment of used oil.

4.7.3 Intermodals with Cold Traps

Sealand-type containers with cold traps containing uranium compounds are stored inside C-746-Q, pending recovery of the uranium. C-746-Q is permitted under the hazardous waste facility permit and is a warehouse structure with a concrete base with curbs. The facility/containers are inspected weekly per the permit for signs of leaks. Spill containment and cleanup supplies are available in the facility.

4.7.4 Storage of UF₆

Bulk UF₆ is stored in on-site cylinders and various facilities around the Paducah Site.

DUF₆ cylinders are stored on concrete pads in the cylinder yards. Storm water runoff from the cylinder yards is channeled to Outfalls 001, 002, 008, 010, 012, 013, 015, and 017 for discharge/monitoring under the KPDES permit (KY0004049).

4.7.5 Storage of Aqueous Hydrogen Fluoride

HF is stored in six aboveground, outdoor, carbon steel 10,000-gal tanks (tanks C-0-HFS-TK-550 to 555) and each tank has the following:

- Polymer lining;
- Remote level monitoring;
- High-level and high-high level alarms to warn operators of potential overfill; and
- Concrete secondary containment (21,166 $\text{ft}^2 \times 3.5$ -ft high, 11,729-gal capacity).

4.7.6 Storage of Posi-Shell[®] Chemicals

Posi-Shell[®] is an alternative daily cover material that is stored at the C-746-U Landfill in metal Sealand containers.

4.7.7 Storage of Flocculants

Flocculants are used for the treatment of suspended solids in the sedimentation pond and are stored in a metal Sealand container at C-746-U Landfill.

4.7.8 Storage of Road Oils and Deicing Materials

The infrastructure contractor is responsible for road maintenance. As such, road salt is stored at the C-732 storage building and in two locations in C-755 Area; C-755-U and C-755-V. Each structure is an approximately 20-ft tall, fully covered, metal storage building with an open front for loading/unloading. The floor of the C-732 storage building is concrete to minimize moisture intrusion and loss of salt material to the environment. The C-755-U and C-755-V storage facilities have rubber barrier pad covers on gravel surface to minimize moisture intrusion and loss of salt material into the environment. Road salt is used during winter months on sidewalks, decks, and steps to improve personal safety. Salt is dissolved in water into a high salinity solution (brine) suitable for road and parking lot pretreatment. If weather is severe enough to defeat the pretreatment, the road salt would be applied directly to road and parking lot surfaces. By using pretreatment, the infrastructure contractor minimizes the amount of salt used and therefore salt runoff to the site's ditches and outfalls.

4.7.9 Storage of Herbicides and Pesticides

The infrastructure contractor utilizes herbicide as one form of weed control and plant management. A minimum amount of concentrate is purchased for use in a one year period. Storage of concentrate is outside in a dedicated "clamshell" weatherproof structure north of C-755-A and C-725. Access to the chemical is restricted by use of a lock and key. Only personnel with current state certifications for herbicide application are allowed to access the chemicals, mix, and apply the chemicals. The herbicide is stored, applied and the container disposed of in accordance with the manufacturer's instructions and Commonwealth of Kentucky law.

4.8 WASTE MANAGEMENT [401 KAR 5:037 § 2(2)(f)]

DOE and its contractors/subcontractors generate, handle, and store a significant quantity of waste materials. Activities that deal with waste are addressed in procedures established to ensure proper storage, maintain accountability, and eliminate the possibility of a release to the environment. At each area of generation, facilities are provided for the proper containerization of waste materials.

Waste handling activities include segregation, transportation, sampling, storage, and treatment and/or disposal. Beginning at generation, wastes are segregated (i.e., liquid from solid) and similar materials are consolidated in containers. To the extent practical, waste is containerized in accordance with 49 *CFR* § 172.101, "Hazardous Material Table," and 49 *CFR* § 173 at the point of generation. This step ensures proper storage and handling until treatment and/or disposal. After wastes are containerized and secured, they are transported to a waste staging or storage area for further processing, transfer to another container, or storage pending treatment and/or disposal. Temporary storage of wastes at the generating project is conducted in accordance with applicable regulations based upon the type of waste [e.g., 40 *CFR* § 262.34 for hazardous wastes, DOE Order 435.1, Chapter 4, for radioactive wastes, and/or 40 *CFR* § 761.65 for wastes containing polychlorinated biphenyls (PCBs)]. Long-term storage of hazardous waste is done in accordance with the hazardous waste facility permit in a facility constructed with concrete secondary containment basins and structures to prevent rain from contacting waste. Long-term storage of other industrial wastes (e.g., radioactive, PCBs) is conducted in the same facilities to the extent practical.

4.8.1 Release Prevention and Control

One of the first steps in preventing groundwater contamination is release prevention. To this end, DOE operates under DOE Order 435.1, Change 1, *Radioactive Waste Management* (DOE 1999), and DOE Order 458.1, Change 3 *Radiation Protection of the Public and the Environment* (DOE 2013), which direct the acceptable conditions for treatment, storage, and disposal of DOE-generated waste. In addition, each project task is required to have a Waste Management Plan, which specifically relates to the expected waste stream, the quantities of waste generated, and also includes, but is not limited to, information on required container inspection, diking, repackaging of waste, and transferring of liquid wastes.

The Environmental Radiological Protection Program (ERPP) is designed to meet the requirements in the DOE Order 458.1, *Radiation Protection of the Public and the Environment*. The purpose of the order is to minimize radiation exposure to the public, control the radiological clearance of property, ensure that any exposure to the public is as low as reasonably possible, monitor routine and nonroutine radiological releases, and to provide protection of the environment from effects of radiation. The ERPP provides an overview of the measures implemented by DOE and its contractors/subcontractors at the Paducah Site.

4.8.2 Release Control

Because the potential for release to the environment exists at all facilities that handle hazardous waste, DOE has developed and continues to update the SPCC Plan. This "living" document stipulates the procedures to be followed and the equipment to be used in the event of a liquid release. It also maintains a record of these releases.

4.9 MATERIAL TRANSFERS [401 KAR 5:037 § 2(2)(p)]

Loading of wastes and/or materials into containers is performed inside of structures to the extent practical. Any spills are promptly cleaned up. Containers are loaded in a manner to avoid/prevent damage to containers during loading/transfer.

Transportation Security Plan for the Transport of Hazardous Materials in Commerce, CP2-WM-0025, has been prepared for waste to be shipped off-site from the D&R Contractor. Procedure DUF6-U-WMP-2001, *Shipping*, has been prepared for off-site shipments of U.S. Department of Transportation (DOT)-regulated hazardous materials except HF. Procedure DUF6-U-WMP-2003, *Hydrogen Fluoride (HF) Shipping*, has been prepared for off-site shipments of HF. These plans/procedures describe the process to ensure

compliance with applicable DOT Hazardous Material Regulations. A hazard classification is assigned to waste/material being shipped in accordance with 49 *CFR* § 172.101 and 49 *CFR* § 173.2a. Waste/material is containerized in accordance with 49 *CFR* § 172.101, *Hazardous Material Table*, and 49 *CFR* § 173. Radiation levels are not allowed to exceed the threshold values provided in 49 *CFR* § 173.441, *Radiation Level*, and 49 *CFR* § 173.443, *Contamination Controls*. Shipping papers are prepared for each shipment in accordance with 49 *CFR* § 172.200 and/or 40 *CFR* § 262. Additional information/shipping papers are provided to comply with applicable requirements of the Nuclear Regulatory Commission, National Emission Standards for Hazardous Air Pollutants, and Toxic Substances Control Act. All marking, labeling, and placarding of waste materials and waste containers are completed in accordance with 40 *CFR* § 172.400, and 49 *CFR* § 172.500, respectively. An Emergency Response Plan is completed and provided for the carrier to use to comply with 49 *CFR* § 171.15, 49 *CFR* § 171.16, and 49 *CFR* § 390.15.

4.10 TREATMENT

4.10.1 Groundwater [401 KAR 5:037 § 2(2)(n)]

The Paducah Site currently operates two groundwater pump-and-treat systems. The Northwest Plume Pump-and-Treat System involves the use of an air stripper, ion exchange units, and a vapor-phase activated carbon exchange unit. The Northeast Plume Containment System uses air strippers. Additionally, projects have been started and/or completed to remediate source contamination at SWMU 1, SWMU 91, C-400, and the Southwest Plume.

4.10.1.1 Northwest Plume Pump-and-Treat System and Northeast Plume Containment System

The groundwater pump-and-treat systems were constructed and are operated in accordance with two separate CERCLA interim records of decision (RODs) approved by EPA. These RODS are the *Record of Decision for Interim Remedial Action of the Northwest Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky* (DOE 1993) and the *Record of Decision for Interim Remedial Action at the Northeast Plume, Paducah Gaseous Diffusion Plant, Paducah, Kentucky* (DOE 1993). The purpose of these facilities is to retard further migration of the northwest and northeast groundwater contaminant plumes. Prior to the implementation of the interim RODs, a water policy was implemented for residences located within the affected areas. This policy was established in an Administrative Consent Order between DOE and EPA, pursuant to Sections 104 and 106 of CERCLA.

Beginning in August 2010, the Northwest Plume Pump-and-Treat System switched from withdrawal from the original four extraction wells to withdrawal from two new extraction wells located at the north boundary of the industrial area of the Paducah Site (in the vicinity of the original south wellfield). The location of these extraction wells was optimized to capture the core and the lateral extent of the Northwest Plume in the area of the north plant boundary. DOE issued an *Explanation of Significant Differences to the Record of Decision for the Interim Remedial Action of the Northwest Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky*, (DOE 2010) for this action in December 2010.

In 2011, the FFA managers identified optimization of the Northeast Plume Containment System as a priority, consistent with the sitewide strategy that includes a series of sequenced activities consisting of source actions and control of off-site groundwater migration followed by a final action for the overall dissolved-phased plume. Subsequently, a resolution to significant differences was finalized in 2016, and a Remedial Action Work Plan was prepared (DOE 2016). Northeast Plume Optimization construction activities commenced in July 2016, and the optimized system was operational in October 2017. The optimized system consists of two new extraction wells moved closer to the known VOC source zones

near the east PGDP security fence in the two centroids of the Northeast Plume. Two new modular air stripper treatment units were installed to treat extracted groundwater from the Northeast Plume.

4.10.1.2 SWMU 91 source remediation

In July 1998, DOE issued the CERCLA *Record of Decision for Remedial Action at Solid Waste Management Unit 91 of Waste Area Group 27 at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky* (DOE 1998). This ROD designated Lasagna[™] as the selected remedial alternative for reducing the concentration of TCE in SWMU 91 to levels that would decrease the potential groundwater risk to human health and the environment at the point of exposure. Installed on the south side of the C-745-B cylinder yard in 1999, the electroosmosis system was operated for two years and reduced the concentration of TCE in SWMU 91 soil from an average of 84 mg/kg to an average of less than 5.6 mg/kg. This was verified in sample results taken in the spring of 2002 and 2003. Additional information about the Lasagna[™] technology and its development can be found in the *Final Soil Characterization Work Plan for the Paducah Gaseous Diffusion Plant Lasagna Pilot Test in the Cylinder Drop Test Area*, (MMES 1994), and the *DNAPL Site Characterization and Lasagna*[™] *Technology Demonstration at Solid Waste Management Unit 91 of the Paducah Gaseous Diffusion Plant, Paducah, Kentucky* (MMES 1996).

4.10.1.3 C-400 source remediation

DOE issued the *Record of Decision for Interim Remedial Action for the Groundwater Operable Unit for the Volatile Organic Compound Contamination at the C-400 Cleaning Building at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky* (DOE 2005), in August 2005. This interim remedial action included the design, installation, operation, and subsequent decommissioning of an electrical resistance heating (ERH) system to heat discrete intervals of the subsurface TCE source zone resulting in volatilization, removal, and recovery of volatile organic compounds from the southern end of the C-400 Cleaning Building. The system became operational in 2010.

The first phase of the ERH was completed in December 2010. Based on the evaluation and the lessons learned from Phase I, it was determined that the ERH base design was successful in reaching target temperatures in the subsurface and removing contaminants in the UCRS and upper RGA. The evaluation of Phase I also indicated that target temperatures were not achieved in the lower RGA (DOE 2011a), which resulted in the split of the Phase II interim remedial action for the southeast source areas into two separate actions: (1) UCRS and Upper RGA action (Phase IIa) and (2) Lower RGA action (Phase IIb). The *Remedial Action Completion Report for the Interim Remedial Action for the Groundwater Operable Unit for the Volatile Organic Compound Contamination at the C-400 Cleaning Building at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky*, (RACR) reported a 95.0% reduction in VOCs in the Phase I east treatment area soils and a 76.0% reduction in VOCs in groundwater within the boundaries of the Phase I east treatment area soils and a 99.0% reduction in VOCs in groundwater within the boundaries of the Phase I southwest treatment area.

Construction of the Phase IIa ERH system was completed in April 2013; remedial ERH operations were initiated in July 2013; and ERH electrodes were turned off in October 2014 to allow the subsurface to cool down, after the FFA parties agreed that asymptosis had been achieved. The soil vapor groundwater treatment system continued to operate through November 2014, at which time operations were ceased, and the remedial action portion of Phase IIa was considered complete. The RACR reported a 99.8% reduction in VOCs in the Phase IIa treatment area soils and a 99.3% reduction in VOCs in groundwater within the boundaries of the Phase IIa treatment area.

The FFA parties signed the *Memorandum of Agreement on the C-400 Complex under the Federal Facility Agreement for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky* (DOE 2017a), in August 2017. The memorandum accelerates the investigation and cleanup of the C-400 Cleaning Building area for all sources of contamination associated with and underlying the C-400 Cleaning Building and integrating the Phase IIb source area into the final action for the C-400 Complex Operable Unit.

4.10.1.4 Southwest Plume source remediation

DOE conducted a site investigation of the Southwest Plume and four potential source areas in 2004, *Site Investigation Report for the Southwest Groundwater Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky* (DOE 2007). As a result, a Focused Feasibility Study for the Southwest Groundwater Plume VOC Sources (Oil Landfarm and C-720 Northeast and Southeast Sites) was conducted (DOE 2011b). Sources to the Southwest Plume included in this action were the SWMU 1 Oil Landfarm, SWMU 211-A C-720 Building TCE Northeast Spill Site, and the SWMU 211-B C-720 Building Southeast Spill Site.

DOE completed a ROD for these Southwest Plume sources in March 2012 (DOE 2012). The ROD for these SWMUs implements deep soil mixing to treat the VOC source zone at SWMU 1. Deep soil mixing at SWMU 1 commenced in March 2015 and concluded in April 2016. The *Remedial Action Completion Report for In Situ Source Treatment by Deep Soil Mixing of the Southwest Groundwater Plume Volatile Organic Source at the C-747-C Oil Landfarm (Solid Waste Management Unit 1), at Paducah Gaseous Diffusion Plant, Paducah, Kentucky (SWMU 1 RACR) reported a 99.0% reduction in VOCs in the treatment area soils (DOE 2017b). The SWMU 1 RACR was approved by EPA and Kentucky in February 2017. The Final Characterization Report Addendum and Letter Notification proposing remedy for 211-A and 211-B were evaluated by the FFA parties. The FFA parties agreed to move forward with 211-A and will determine an appropriate remedial action for 211-B, based on a revised conceptual site model consistent with the data in the Final Characterization Report.*

4.10.2 Decontamination, Well Development, and Well Purge Wastewater [401 KAR 5:037 § 2(2)(n)]

C-752-C is a large concrete containment pad covered by a roof. This facility is used to decontaminate equipment and to treat wastewaters to remove suspended solids in accordance with the KPDES permit. This treatment usually serves as pretreatment for water that is further treated in the C-612 facility.

4.10.3 C-746-S and C-746-U Landfill Leachate [401 KAR 5:037 § 2(2)(n)]

The C-746-U-15 leachate treatment system has a large concrete secondary containment pad covered by a permanent structure. Wet wells in this facility are designed to automatically pump any releases back into the influent tank. This facility treats C-746-S and C-746-U Landfill leachate using treatment media prior to discharge in accordance with the solid waste landfill permit. The leachate discharge is regulated under the KPDES permit.

4.10.4 Miscellaneous Wastewater [401 KAR 5:037 § 2(2)(n)]

The C-752-A permitted hazardous waste treatment facility has a large concrete secondary containment pad covered by a permanent structure. This facility also is used to treat miscellaneous wastewaters generated at the Paducah Site such as decontamination solutions, contamination storm waters, leachate from C-404 or C-746-U, etc., in accordance with the KPDES permit. Treatment in this facility includes chemical precipitation, photocatalytic reaction, particulate filtration, and/or carbon filtration.

4.10.5 Noncontact Cooling Water [401 KAR 5:037 § 2(2)(n)]

The DUF₆ Conversion Facility cooling tower blowdown contains a biocide and deposit control agent and is discharged through the effluent treatment system in accordance with the KPDES permit.

4.10.6 C-613 Storm Water Control Basin [401 KAR 5:037 § 2(2)(0)]

C-613 collects storm water from the northeast part of the PGDP limited area. This facility originally was constructed to contain contaminated runoff from the scrap metal yards under CERCLA. The basin is lined to minimize migration of contaminants to groundwater. The basin is approved under the KPDES permit (KY0004049) to treat wastewater with high levels of suspended contaminants prior to discharge through Outfall 001.

4.10.7 Use of Surface Impoundments, Lagoons, Ditches in CERCLA Projects [401 KAR 5:037 § 2(2)(0)]

Many of the remediation projects require the holding/collecting of storm waters to prevent/minimize contaminated runoff. Specific control measures and technologies are addressed in the project specific CERCLA work plan.

5. IMPLEMENTATION SCHEDULE

The controls and measures described in this plan have been established in accordance with regulatory requirements and, as a result, already have been implemented.

6. EMPLOYEE TRAINING

DOE ensures that contractor personnel are trained and qualified for their functional positions. Each contractor employee has an individualized Training Position Description (TPD). Each contractor employee is required to complete his/her assigned training prior to implementing any work associated with their respective TPD. This training complies with state and federal regulations, DOE orders, contractor policies and procedures, and the Paducah Site, site-specific requirements, as applicable. This training ensures that all employees implement proper practices for protection of the environment, including groundwater protection. Applicable training courses include the following:

- General Employee Training (GET): This training session covers general topics for performing work at a DOE facility, including the Quality Assurance Program, classification security, the Industrial Hygiene Program, emergency preparedness, fire protection, Radiological Program, criticality safety, and hazard communication. Training includes elements on storage and use of hazardous materials. Many of these topics incorporate the requirements for groundwater protection measures required for work conducted at the Paducah Site. Personnel who require access to the Paducah Site, except escorted visitors, must complete this course. Testing is required to complete the course and it must be renewed every two years. GET consists of Web-based training.
- **Consolidated Annual Training (CAT):** This training session covers general topics for performing work at a DOE facility, including the ISMS/EMS, Quality Assurance Program, use of fire extinguishers, and waste minimization/management. These are key components for the overall environmental management activities conducted at the Paducah Site in support of groundwater and other environmental protection programs. Testing is required to complete the course, and it must be renewed every year. CAT consists of Web-based training.
- Radiological Worker Training I and II: Radiological Worker Training is required for all unescorted personnel who work in, or require access to, radiological areas. Radiological areas, as defined by the site Radiological Control Program procedures, include contamination areas, high contamination areas, radiation areas, high radiation areas, very high radiation areas, airborne radioactivity areas, radioactive material areas, fixed contamination areas, underground radioactive material areas, and radiological buffer areas. Training focuses on spread of contaminants, which prevents potential for discharge to groundwater. This training is designed to be accomplished in approximately 16 hours; however, the core material may be reviewed as self-study followed by a Web-based examination. This training must be recertified every two years.
- Waste Generator Training: The following training is required for personnel who generate, package, and handle RCRA-hazardous waste, including personnel who work in areas that generate hazardous waste and who manage satellite or 90-day accumulation areas: Fissile/Potentially Fissile Waste Handling and Storage Requirements; PCB Awareness training; DOT General Awareness Training, Nevada National Security Site Waste Acceptance, Hazardous Waste Training, Transportation Security Plan, DOT Identification of Hazardous Waste, RCRA Permit B, DOT Packaging Operator, DOE 0.435.1 Implementation, HAZMAT Transportation Security Awareness, and Suspect/ Counterfeit Item Awareness. This training gives instruction on the proper identification, management, and temporary storage of wastes generated during the performance of hazardous waste activities at the Paducah Site. In addition, the following required reading documents are assigned to personnel handling and managing waste: FRNP Waste Management Plan; NNSS Specific Waste Characterization, Profiling, Packaging, and Shipping; Safe Handling and Opening of Sealed Containers; Generation and Temporary Storage of Waste Materials; Waste Container Handling, Overpacking, and Transportation; Waste Packaging; and PCB Spill Management-Waste

Management. Proper waste management minimizes the risk of a release of contaminants to groundwater at the Paducah Site.

• **Hazard Communication Training:** Hazard Communication Training is required for personnel who use or might come in contact with hazardous materials defined under the Occupational Safety and Health Act. The course covers appropriate identification, storage, use, and labeling. This is a one-time course with refresher training required annually, with additional requirements for supervisory personnel. Proper hazardous materials management minimizes the risk of a release of hazardous materials to groundwater at the Paducah Site.

7. INSPECTION SCHEDULE

Inspections of each system for control of groundwater pollution are unique to each type of activity. Inspection forms are driven by the SPCC Plan; the Hazardous Waste Facility Permit; and the Solid Waste Permit. Pursuant to each of those requirements, the checklists include the date, name of operator and supervisor, what the inspection pertains to, observations, and any actions taken. An example inspection form for oil-containing tanks, containers, and equipment is shown on the following page.

EXAMPLE FORM

CP4-OP-1124-F01 – Chemical Operations Operator Rounds and Equipment Status Sheet

Date:	Time:					
		LOCATION	OK			
C-400	BUILDING [Including brea	akrooms/changehouses/process areas/basement, etc.]				
Water Le	aks					
Air Leak	S					
Lighting						
	d 480 Volt heater cord connections section and notify Supervisor.)	s checked $<110^{\circ}$ F. (Note heater locations where connections are $>110^{\circ}$ F in				
C-400	CAAS AIR BOOSTER CO	MPRESSOR	•			
Check ai	r pressure on PI-136. If pressure ≥	≥ 158.0 psig and compressor is running, then notify Supervisor.				
*Oil is a	top of circle within bull's eye who	en compressor is shut down				
CAAS C	ompressor hour meter reading					
C-409	BUILDING (Including brea	akrooms/change houses/process area, etc.)				
Water le	ıks					
Air leaks						
***Light		MDDESSOD				
	CAAS AIR BOOSTER CO	≥ 158.0 psig and compressor is running, then notify Supervisor.				
	top of circle within bull's eye whe					
	ompressor hour meter reading					
	D/C-410-K					
No evide	nce of fluorine leakage in area or e	equipment				
	alarm check performed	<u> </u>				
C-410-	D CAAS AIR BOOSTER C	COMPRESSOR				
Check ai	r pressure on PI-136. If pressure ≥	≥ 158.0 psig and compressor is running, then notify Supervisor.				
*Oil is a	top of circle within bull's eye whe	en compressor is shut down				
CAAS C	ompressor hour meter reading					
C-410-	D AND C-410-K FLUORIN	NE AREAS				
P R	Tank A (Max. 148 psia Min. 16	6 psia)				
E S S U	Tank B (Max. 148 psia Min. 16	6 psia)				
U R	Tank C (Max. 148 psia Min. 16	6 psia)				
E S	Header (Max. 22.7 psia Min. 1	5 psia)				
No evide	nce of leakage from tube truck					
C-742-	B ClF ₃ Cylinder Storage Ya	ard				
No comb	ustible waste or excessive vegetati	ion within 10 feet of cylinders				
Cylinder	labels, barricades and postings are	e free from damage and are legible				
C-745-	A-1 F ₂ Tube Truck					
No evide	nce of leakage from tube truck					
No evide	nce of damage to tubing or valves					
Truck labels and posting are free from damage and legible						

CP4-OP-1124-F01 - Chemical Operations Operator Rounds and Equipment Status Sheet

[LOCATION		OK
C-410 L SPILL RESPONSE AREA			
Sliding door is sealed with TID and locked			
Comments:			
Operator signature:	Badge #	Date	
Supervisor signature:	Badge #	Date	

* If oil below circle inside bull's eye, then add oil according to CP3-OP-0301. If above inside bull's eye, then notify Supervisor. ** Not required when truck is in winter storage. *** Excludes lighting above C-409 Uranium Recovery Area

CP4-OP-1124-F01, FRev. 1

8. CERTIFICATION STATEMENT

DOCUMENTATION IDENTIFICATION:

Groundwater Protection Plan for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, PAD-PROJ-0018/FR2

I, Myrna E. Redfield, Four Rivers Nuclear Partnership, LLC, Acting Program Manager, certify that this Groundwater Protection Plan complies with the requirements of 401 *KAR* 5:037. I have read the terms of the plan and will implement its provisions.

Signature: Date:

9. REVIEW LOCATION FOR GROUNDWATER PROTECTION PLAN

Public inspection of GPPs is a provision of 401 *KAR* 5:037 § 4(7). This plan is made available for access at the following website: <u>https://fourriversnuclear.com/public-documents/all</u>. Hard copies may be requested through the Paducah Environmental Information Center at the address listed below.

5100 Alben Barkley Drive Emerging Technology Center, Room 221, Paducah, Kentucky 42001 Phone: (270) 554-3004 Hours: Monday through Friday from 8 a.m. to 12 p.m.

10. REFERENCES

- DOE (U.S. Department of Energy) 1993. Record of Decision for Interim Remedial Action of the Northwest Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/OR/06-1143&D4, U.S. Department of Energy, Paducah, KY, July.
- DOE 1995. Record of Decision for Interim Remedial Action at the Northeast Plume, Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/OR/06-1356&D2, U.S. Department of Energy, Paducah, KY, June.
- DOE 1998. Record of Decision for Remedial Action at Solid Waste Management Unit 91 of Waste Area Group 27 at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/OR/06-1527&D2, U.S. Department of Energy, Paducah, KY, July.
- DOE 1999. *Radioactive Waste Management*, DOE Order 435.1, Change 1, U.S. Department of Energy, Washington, DC, January.
- DOE 2005. Record of Decision for Interim Remedial Action for the Groundwater Operable Unit for the Volatile Organic Compound Contamination at the C-400 Cleaning Building at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/OR/07-2150&D2/R2, U.S. Department of Energy, Paducah, KY, July.
- DOE 2007. Site Investigation Report for the Southwest Groundwater Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/OR/07-2180&D2/R1, U.S. Department of Energy, Paducah, KY, June.
- DOE 2010. Explanation of Significant Differences to the Record of Decision for the Interim Remedial Action of the Northwest Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/LX/07-0343&D2, U.S. Department of Energy, Paducah, KY, December.
- DOE 2011a. Technical Performance Evaluation for Phase I of the C-400 Interim Remedial Action at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/LX/07-1260&D1, U.S. Department of Energy, Paducah, KY, August.
- DOE 2011b. Revised Focused Feasibility Study for Solid Waste Management Units 1, 211A, and 211B Volatile Organic Compound Sources for the Southwest Groundwater Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/LX/07-0362&D2, U.S. Department of Energy, Paducah, KY, May.
- DOE 2012. Record of Decision for Solid Waste Management Units 1, 211-A, 211-B, and Part of 102 Volatile Organic Compound Sources for the Southwest Groundwater Plume at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/LX/07-0365&D2/R1, U.S. Department of Energy, Paducah, KY, March.
- DOE 2013. *Radiation Protection of the Public and the Environment*, DOE Order 458.1, Change 3, U.S. Department of Energy, Washington, DC, January.
- DOE 2016. Remedial Action Work Plan for Optimization of the Northeast Plume Interim Remedial Action at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/LX/07-1280&D2/R3, U.S. Department of Energy, Paducah, KY, April.

- DOE 2017a. Memorandum of Agreement on the C-400 Complex under the Federal Facility Agreement for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, PPPO-02-4394247-17, U.S. Department of Energy, Paducah, KY, August.
- DOE 2017b. Remedial Action Completion Report for In Situ Source Treatment by Deep Soil Mixing of the Southwest Groundwater Plume Volatile Organic Source at the C-747-C Oil Landfarm (Solid Waste Management Unit 1), at Paducah Gaseous Diffusion Plant, Paducah, Kentucky, DOE/LX/07-2405&D2, U.S. Department of Energy, Paducah, KY, January.
- DOE 2018. Remedial Action Completion Report for the Interim Remedial Action for the Groundwater Operable Unit for the Volatile Organic Compound Contamination at the C-400 Cleaning Building at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky DOE/LX/07-2417&D2, U.S. Department of Energy, Paducah, KY, July.
- Finch 1967. Finch, W. I., *Geologic Map of Part of the Joppa Quadrangle, McCracken County, Kentucky.* GQ-652, U.S. Department of the Interior, U.S. Geological Survey.
- FRNP (Four Rivers Nuclear Partnership, LLC) 2018a. Spill Prevention, Control, and Countermeasure Plan for the U.S. Department of Energy Paducah Site, McCracken County, Kentucky, PAD-REG-1005/R3, Four Rivers Nuclear Partnership, LLC, Kevil, KY, April.
- FRNP 2018b. Environmental Monitoring Plan Fiscal Year 2018, Paducah Gaseous Diffusion Plant, Paducah, Kentucky, CP2-ES-0006/FR1, Four Rivers Nuclear Partnership LLC, Kevil, KY, January.
- FRNP 2018c. Best Management Practices Plan, Paducah Gaseous Diffusion Plant, Paducah, Kentucky, PAD-REG-1006/FR2, Four Rivers Nuclear Partnership, LLC, Kevil, KY, May.
- Frye 1972. Frye, J. C., et al. *Geology and Paleontology of Late Pleistocene Lake Saline, Southeastern Illinois*. Circular 471, Illinois State Geological Survey, Champaign, IL, June.
- KDEP (Kentucky Department for Environmental Protection) 2018. Guidance Document, *Preparing a Groundwater Protection Plan*, Kentucky Department for Environmental Protection, Frankfort, KY, <u>http://water.ky.gov/groundwater/Pages/GroundwaterProtectionPlans.aspx</u> (accessed March 15, 2018).
- LATA (LATA Environmental Services of Kentucky, LLC) 2015. Groundwater Protection Plan for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky, PAD-PROJ-0018/R2, LATA Environmental Services of Kentucky, LLC, Paducah, May.
- MCS (Mid-America Conversion Services, LLC) 2017. Paducah Storm Water Pollution Prevention and Best Management Practices Plan, DUF6-PLN-079/R1, Mid-America Conversion Services, LLC, Paducah, KY, November.
- MMES (Martin Marietta Energy Systems, Inc.) 1994. *Final Soil Characterization Work Plan for the Paducah Gaseous Diffusion Plant Lasagna Pilot Test in the Cylinder Drop Test Area*, KY/ER-57, Martin Marietta Energy Systems, Inc., Paducah, KY, May.

- MMES 1996. DNAPL Site Characterization and Lasagna[™] Technology Demonstration at Solid Waste Management Unit 91 of the Paducah Gaseous Diffusion Plant, Kentucky, KY/EM-128, Martin Marietta Energy Systems, Inc., Paducah, KY, March.
- USDA (U.S. Department of Agriculture) 1976. Soil Survey of Ballard and McCracken Counties, Kentucky. U.S. Department of Agriculture Soil Conservation Service in cooperation with the Kentucky Agricultural Experiment Station, February.
- USGS (United States Geological Survey) 1980. *Geologic Maps of the Jackson Purchase Region, Kentucky*, Miscellaneous Investigations Series, MAP I-1217, Reston, VA.

APPENDIX A


DOE PADUCAH SITE FIGURES AND TABLE

FIGURES


A.1.	Paducah Gaseous Diffusion Plant Site Map	.A-5
	Paducah Site Map Showing Current SWMU Locations	
A.3.	2016 TCE Plume—Regional Gravel Aquifer	4-29
	2016 Tc-99 Plume—Regional Gravel Aquifer	


TABLE

A.1.	Solid Waste Management	Units/Areas of Concern	h by Operable Un	itA-9



	FACILITY			FACILITY			FACILITY	ITE INDEX		FACILITY		
	NUMBER C-100 C-100-B	ADMINISTRATION BUILDING STORAGE AREA	G-11 G-11	C-607	EMERGENCY AIR COMPRESSOR GENERATOR BUILDING	F-9 C-10	NUMBER C-728 C-729	MOTOR CLEANING FACILITY ACETYLENE BUILDING	LOCATION F-9 G-10	NUMBER C-755-T04 C-755-T05	OFFICE TRAILER OFFICE TRAILER	LOCATION K-9 J-9
	C-100-T04 C-100-T05 C-100-T06	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	G-11 G-11 G-11	C-611-A1 C-611-B	ACTIVATED CARBON STORAGE BUILDING	C-10 C-11 C-10	C-730 C-730-A C-730-C	MAINTENANCE SERVICES STORM SHELTER EAST GRAVEL PARKING AREA	F-10 F-11 F-11	C-755-T06 C-755-T07 C-755-T08B	OFFICE TRAILER OFFICE TRAILER SHOWER & CHANGE ROOM	K-9 K-9 K-9
	C-100-T08 C-101 C-102	FOCI OFFICE & CHANGE HOUSE FORMER CAFETERIA HOSPITAL	G-11 G-11 G-11	C-611-B1 C-611-C C-611-D	POLYMER FEED SYSTEM ENCLOSURE FLOCCULATOR BASIN	C-10 C-10 C-10 C-10	C-730-D C-730-T01 C-730-T02	WEST GRAVEL PARKING AREA OFFICE TRAILER OFFICE TRAILER	E-11 F-10 F-10	C-755-T09 C-755-T10 C-755-T11	OFFICE TRAILER STORAGE TRAILER STORAGE TRAILER	J-9 K-9 K-9
00	C-102-T01 C-102-T02 C-102-T03	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	G-10 G-10 G-10	C-611-E C-611-F	SETTLING BASIN (NORTHWEST) SETTLING BASIN (SOUTHEAST)	C-10 C-10	C-730-T05 C-730-T06 C-731	OFFICE TRAILER OFFICE TRAILER RAILROAD REPAIR EQUIPMENT	F-11 F-11 E-9	C-755-T12 C-755-T13 C-755-T14	STORAGE TRAILER SEALAND STORAGE SEALAND STORAGE	K-9 J-9 J-9
	C-102-T04 C-102-T05 C-103	OFFICE TRAILER OFFICE TRAILER DOE SITE OFFICE & ANNEX	G-10 G-10 F-12	C-611-F1 C-611-F2 C-611-F3	SECONDARY COAGULATION BASIN CHEMICAL FEED FOR C-611-F1 ACTIVATED CARBON FEED	C-11 C-11 C-11	C-731	STORAGE BUILDING MAINTENANCE MATERIALS STORAGE BUILDING (SALT)	E-9	C-755-T15 C-755-T16 C-755-T17A	SEALAND STORAGE RADCON TRAILER CHANGEHOUSE / SHOWER TRAILER	J-9 J-9 J-9
	C-103-C C-103-PL C-200	CONCRETE PAD AND CANOPY DOE SITE OFFICE PARKING AREA GUARD & FIRE HEADQUARTERS	F-12 F-12 G-10	C-611-G C-611-H C-611-I	SETTLING BASIN (SOUTHWEST) FILTER BUILDING & PUMP STATION CLEAR WELL	C-11 C-11 C-11	C-733 C-740	WASTE OIL & CHEMICAL STORAGE FACILITY MATERIAL YARD	E-9 E-10	C-755-T18 C-755-T19 C-755-T20	FIELD OFFICE TRAILER OFFICE BREAK TRAILER OFFICE BREAK TRAILER	J-9 J-9 J-9
00	C-200-A C-200-B	C-200 ANNEX STORAGE TRAILER EMERGENCY EQUIPMENT	G-10 G-10 G-10	C-611-J C-611-K C-611-O	PUMP HOUSE (SETTLED WATER) LAGOON No. 4 SANITARY WATER STORAGE TANK	C-11 C-10 I-9	C-740-A C-740-B C-741	SEMI-TRAILER UNLOADING FACILITY OIL DRUM STORAGE SHELTER MOBILE EQUIPMENT SHED	E-10 E-10 F-10	C-755-T21 C-755-T22A	OFFICE TRAILER INSTRUMENT LAB TRAILER OFFICE TRAILER	J-9 J-9
	C-201 C-202 C-203	STORAGE BUILDING GUARD TRAINING BUILDING EMERGENCY VEHICLE SHELTER	G-10 G-10 G-10	C-611-Q C-611-R	36" RAW WATER LINE BOOSTER STATION HIGH PRESSURE FIRE WATER TANK	H-6 I-9	C-742 C-742-B C-743	CYLINDER STORAGE BUILDING CI F3 CYLINDER STORAGE OFFICE BUILDING	F-10 D-8 E-10	C-755-T23 C-755-T24 C-755-T25	SEALAND STORAGE SEALAND STORAGE	J-9 K-9 K-9
	C-204 C-205 C-206	DISINTEGRATOR BUILDING RESPIRATOR ISSUE BUILDING PUMPER DRAFTING PIT	G-10 G-10 E-10	C-611-S C-611-T	CL2 STORAGE & FEED BUILDING BOOSTER PUMP STATION (PLANT WATER)	C-11 F-10	C-743-A C-743-A1 C-743-A2	HEALTH PHYSICS STORAGE STORAGE SHED STORAGE SHED	E-10 E-10 E-10	C-755-T26 C-755-T27 C-755-T28	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	J-9 J-9 J-9
00	C-206-B C-207	SMOKE TRAINING FACILITY - CONDEMNED FIRE TRAINING FACILITY	E-10 E-10 E-10	C-611-T01 C-611-U C-611-V	SOFTENING FACILITY (WEST) SLUDGE LAGOON	C-11 C-10 C-9	C-743-B C-743-C C-743-D	STORM SHELTER STORM SHELTER WOODEN STORAGE BLDG.	E-10 E-10 E-10	C-755-A C-755-A1 C-755-B	MAINTENANCE SHOP STORAGE SHED CHANGE HOUSE BUILDING	J-9 J-9 K-9
B	C-215-M C-218 C-223	IMAC PORTAL ACCESS FIRING RANGE (Out of Service) POST 49 BUILDING	G-10 D-10 G-13	C-611-V1 C-611-W C-611-X	SOFTENING FACILITY (EAST)	C-9 C-10 C-10	C-743-T01 C-743-T02 C-743-T03	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	F-10 F-10 E-10	C-755-C C-755-D C-755-E	EM STORAGE FACILITY GUARD SHACK UNDERGROUND STORM SHELTER	J-9 K-9 J-9
00	C-224 C-225	MAIN GUARD POST 15 BUILDING POST 48 BUILDING GRAVEL PARKING AREA	G-11 J-9	C-611-Y C-611-Z C-612	PILOT PUMP AND TREAT	C-9 C-10 D-7	C-743-T04 C-743-T07 C-743-T09	CHANGE HOUSE/SHOWER TRAILER OFFICE TRAILER OFFICE TRAILER	E-10 E-10 F-10	C-755-F C-755-G C-755-H	UNDERGROUND STORM SHELTER UNDERGROUND STORM SHELTER UNDERGROUND STORM SHELTER	J-9 K-9 J-9
	C-225-A C-226 C-228	WEST OF C-755-P GUARD SHACK (POST 91) GUARD TOWER (POST 93)	J-9 H-10 J-9	C-612-A C-612-B C-612-T01	PUMP AND TREAT DECON PAD STORM SHELTER PUMP AND TREAT OFFICE	D-7 D-7 D-7	C-743-T11 C-743-T12 C-743-T13	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	E-10 E-10 E-10	C-755-M C-755-M1 C-755-M2	STORAGE BUILDING STORAGE BUILDING STORAGE BUILDING	K-9 J-9 J-9
•	C-233 C-300 C-301	POST 233 TRAILER CENTRAL CONTROL BUILDING FIRE TRAINING BUILDING	D-10 H-10 I-9	C-612-T02 C-612-T03 C-612-T04	PUMP AND TREAT OFFICE PUMP AND TREAT CHANGEHOUSE WOODEN STORAGE BUILDING	D-7 D-7 D-7	C-743-T14 C-743-T15 C-743-T16	OFFICE TRAILER OFFICE TRAILER MATERIAL HANDLING TRAILER	E-10 E-10 E-10	C-755-M3 C-755-M4 C-755-N	STORAGE BUILDING STORAGE SHED EAST EXTENDED PARKING LOT	J-9 K-9 K-9
00	C-302 C-303	OPERATIONS DIV. DATA CENTER SUPERVISORY CONTROL & DATA ACQUISITION SYSTEM	G-10 H-10	C-612 -T05 - T08 C-612 -T09 - T12	SEALAND STORAGE TRAILERS SEALAND STORAGE TRAILERS	D-7 D-7	C-743-T17 C-743-T17A C-743-T18	FIELD SUPPORT LAB TRAILER FIELD SUPPORT & LAB SHELTER SHED	E-10 E-10 E-10	C-755-P C-755-R C-755-S	GRAVEL PARKING LOT SEALAND STORAGE OFFICE TRAILER	J-9 K-9 K-9
	C-304 C-310	TRAINING & CASCADE OFFICE BUILDING PURGE & PRODUCT BUILDING	H-10 H-10	C-613 C-613-A C-613-B	SCRAP YARD SEDIMENTATION BASIN PROCESS AND OFFICE TRAILER SOIL BORROW STOCKPILE	D-7 D-7 D-7	C-744 C-745-A C-745-A1	LUBRICATION BUILDING CYLINDER STORAGE YARD FLUORINE STORAGE YARD	F-9 E-9 D-9	C-755-T C-755-U C-755-V	STORAGE SHED EQUIPMENT SHEDS (8) SALT STORAGE	K-9 J-9 K-9
	C-310-331 C-310-331-A C-310-331-B	TIE LINE BRIDGE (ENCLOSED) TIE LINE	H-9 H-10 H-10	C-613-01 C-613-02	BASIN PUMP STATION BASIN PUMP STATION NORTHEAST PLUME	D-8 D-8	C-745-A-SW C-745-B	CYLINDER STORAGE CYLINDER STORAGE YARD	D-9 E-8	C-755-W C-755-X C-755-Z	OFFICE TRAILER STORAGE SHED STORAGE TRAILER	K-9 K-9 K-9
00	C-310-A C-315 C-315-331	PRODUCT WITHDRAWAL BUILDING SURGE & WASTE BUILDING TIE LINE	H-10 I-10 I-10	C-614 C-614-A C-614-B	TREATMENT SYSTEM NORTHEAST PLUME PAD NORTHEAST PLUME	M-7 M-7 M-7	C-745-B1 C-745-C C-745-C-T03	CYLINDER STORAGE YARD OFFICE CYLINDER STORAGE YARD OFFICE TRAILER	E-8 F-8 F-8	C-757 C-759	SOLID & LL WASTE PROCESS FACILITY SCRAP METAL STAGING AREA	G-7 F-8
	C-315 C-320 C-331	PROPANE TANKS COMMUNICATION BUILDING PROCESS BUILDING	I-10 H-10 I-10	C-614-C	EXTRACTION WELL 331 NORTHEAST PLUME EXTRACTION WELL 332	M-7	C-745-E C-745-F	CYLINDER and OXIDE STORAGE YARD CYLINDER STORAGE YARD CYLINDER STORAGE YARD	I-13 J-9 H-12	C-759-A C-760	ISOCS - In Situ Object Counting System North-South Diversion Ditch (NSDD) LAYDOWN GRAVEL PAD	F-8 G-7
	C-331-333-A C-331-333-B C-331-333-C	BRIDGE (ENCLOSED-300 FT) TIE LINE (EAST) TIE LINE (WEST)	H-10 H-10 I-10	C-614 -FENCE C-615 C-615-A		M-7 D-10 D-10		CYLINDER STORAGE YARD BASIN LIFT STATION TEMPORARY CYLINDER PAINT FACILITY		C-760-A C-761 C-762	NSDD SURGE BASIN WASTE DISPOSITION STAGING EQUIPMENT STAGING PAD	G-7 G-14 J-6
00	C-331-335 C-331-A C-331-B	TIE LINE CONTRACTOR STAGING YARD, WEST CONTRACTOR STAGING YARD, EAST	H-9 I-9 J-9	C-615-B C-615-C C-615-D	FINAL SETTLING TANK OIL CONTROL BUILDING	D-10 D-10 D-10	C-745-G4	TEMPORARY CYLINDER PAINT FACILITY TEMPORARY CYLINDER PAINT FACILITY TEMPORARY CYLINDER PAINT FACILITY	′ H-12	C-764-A C-764-B C-764-C1	PARKING AREA SANITARY WATER VAULT SANITARY WATER VAULT	D-10 E-10 E-10
,	C-331-C C-333 C-333-A	GRAVEL PARKING/STAGING AREA PROCESS BUILDING FEED VAPORIZATION FACILITY	I-9 H-11 H-12	C-615-E C-615-F C-615-G	TRICKLING FILTER TRICKLING FILTER SLUDGE BEDS	D-10 D-10 G-10	C-745-H C-745-J	CYLINDER STORAGE YARD RADIOACTIVE MATERIAL STORAGE YARD	J-7 J-7	C-764-T01 C-764-T02 C-764-T03	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	D-10 D-10 D-10
	C-335-A C-335-337-A C-335-337-B	PROCESS BUILDING BRIDGE (ENCLOSED) TIE LINE (NORTH)	H-8 H-8 H-8	C-615-H C-615-H1 C-615-H2	SEWAGE LIFT STATION SEWAGE LIFT STATION SEWAGE LIFT STATION	G-8 J-9 G-8	C-745-K C-745-L C-745-M	CYLINDER STORAGE YARD CYLINDER STORAGE YARD CYLINDER STORAGE YARD	H-13 H-13 H-13	C-764-T04 C-764-T05 C-764-T06	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	D-10 D-10 D-10
	C-335-337-B C-335-337-C C-337 C-337-A	TIE LINE (NORTH) TIE LINE (SOUTH) PROCESS BUILDING FEED VAPORIZATION FACILITY	H-8 I-8 I-8	C-615-H3 C-615-H4 C-615-H4A	SEWAGE LIFT STATION SEWAGE LIFT STATION	J-9 G-12 F-12	C-745-N C-745-OXE C-745-P	CYLINDER STORAGE YARD OXIDE STORAGE YARD CYLINDER STORAGE YARD	I-13 I-13 I-13	C-764-T07 C-764-T08 C-764-T09	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	D-10 D-10 D-10
2	C-350 C-360	DRYING AGENT STORAGE BUILDING TOLL TRANSFER & SAMPLING BUILDING	H-9 J-9	C-615-H5 C-615-H6	SEWAGE LIFT STATION SEWAGE LIFT STATION SEWAGE LIFT STATION CHROMATE LIFT STATION	J-9 E-7	C-745-Q C-745-R C-745-R1	CYLINDER STORAGE YARD CYLINDER STORAGE YARD CYLINDER CHANGEOUT BUILDING	I-12 I-12 I-13	C-764-T10 C-764-T11 C-765	OFFICE TRAILER CHANGE HOUSE TRAILER NE PLUME ALT. TREATMENT SYSTEM	E-10 E-10 K-8
	C-360-A C-400	TOLL TRANSFER & SAMPLING BUILDING ANNEX CLEANING BUILDING	J-9 G-9	C-615-H7 C-615-H8 C-615-J	(ABANDONED) OIL CONTROL MONITORING STATION	H-8 J-9 H-10	C-745-S C-745-T C-745-U	CYLINDER STORAGE YARD CYLINDER STORAGE YARD CYLINDER STORAGE YARD	H-13 I-14 I-13	C-765-A C-770	NE PLUME CONTAINMENT SYSTEM STAGING AREA - former VORTEC DEMONSTRATION PLANT	J-9 D-8
00	C-400-A C-400-C	EMERGENCY POWER FOR CRITICAL ALARMS GROUNDWATER TREATMENT	G-9 G-9	C-615-K C-615-L	CHROMATE LIFT STATION (ABANDONED) OIL CONTROL BUILDING	G-8 D-9	C-745-V C-745-W	CYLINDER STORAGE YARD CYLINDER YARD HIGH ACTIVITY R.R. PAD	J-13 I-13	C-800 C-802 C-802-A	MOTORCYLCE PARKING SHELTER METEOROLOGICAL TOWER RADIO COMMUNICATION BUILDING	G-11 G-12 G-12
	C-400-D C-400-L	SYSTEM BUILDING LIME PRECIPITATION & ION EXCHANGE UNIT STORM WATER LIFT STATION	G-9 G-8	C-615-M C-615-N C-615-O	OIL CONTROL STRUCTURE OIL CONTAINMENT LAGOON OIL CONTROL BUILDING	D-9 D-9 D-9	C-745-X C-745-Y C-745-Z	EQUIPMENT STORAGE YARD EQUIPMENT STORAGE YARD EQUIPMENT STORAGE YARD	I-12 J-8 J-8	C-802-B C-810	METEOROLOGICAL EQUIPMENT BUILDING PARKING AREA (C-100)	G-12 G-11
00	C-400-L C-400-T01 C-400-T02 C-403	TRAILER TRAILER NEUTRALIZING PIT	G-9 G-9 G-9 G-9	C-616 C-616-A	LIQUID POLLUTION ABATEMENT FACILITY CHEMICAL FEED BUILDING	F-7 G-7	C-745-Z1 C-746 C-746-A	CONSTRUCTION SPOILS AREA ABANDONED GE BETZ TANK NORTH WAREHOUSE (METAL FURNACE & SCRAP RECOVERY)	J-7 E-8 F-7	C-811	PARKING AREA (C-720) Depleted Uranium	F-11 G-12
	C-404 C-404-A	LOW-LEVEL RADIOACTIVE WASTE BURIAL AREA SUMP	F-8 F-8	C-616-B C-616-C C-616-D	CLARIFIER (EAST) LIFT STATION SLUDGE LAGOON & VALVE PIT	G-7 G-7 G-7	C-746-B1 C-746-B-T01 C-746-C	STAGING AREA OFFICE TRAILER CLEAN SCRAP YARD (NORTH)) F-7 F-7 F-7	C-1100 C-1100-SS01	Hexafluoride (DUF ₆) Conversion ADMINISTRATION BUILDING STORM SHELTERS	G-13 G-13
0	C-407 C-409 C-410-D	NITRIC ACID STORAGE TANK STABILIZATION BUILDING F2 STORAGE BUILDING	G-9 G-9 H-9	C-616-E C-616-F C-616-H1	SLUDGE LAGOON FULL FLOW LAGOON FESO4 STORAGE TANK (EAST)	F-6 F-6 G-7	C-746-C1 C-746-D	CLEAN SCRAP YARD (SOUTH) CLASSIFIED SCRAP YARD CONTAMINATED SCRAP YARD (NORTH)	F-7 J-9	C-1100-SS02 C-1100-T01 C-1100-T02	ADMIN TRAILER ADMIN TRAILER	G-13 G-13 G-13
00	C-410-K C-410-L C-411-A	FLUORINE FACILITY BUILDING QUONSET HUT STAGING AREA	H-9 H-9 H-9	C-616-H2 C-616-J C-616-K	FESO4 STORAGE TANK (WEST)REDUCTION TANK (EAST)CHEMICAL FEED STORAGE BUILDING	G-7 G-7 G-7		CONTAMINATED SCRAP YARD (SOUTH) CLASSIFIED SCRAP BURIAL YARD ELECTRICAL EQUIPMENT STORAGE		C-1100-T03 C-1100-T04 C-1100-T05	ADMIN TRAILER ADMIN TRAILER ADMIN TRAILER	G-13 G-13 G-12
	C-412 C-412-T01 C-412-T02	TRAILER COMPLEX OFFICE TRAILER OFFICE TRAILER	G-10 G-10 G-10	C-616-L C-616-M C-616-N	EFFLUENT CONTROL VAULT CLARIFIER (WEST) REDUCTION TANK (WEST)	G-9 F-7 F-7	C-746-G-T01 C-746-H1 C-746-H2		J-9 F-9 F-9	C-1100-T06 C-1100-T09 C-1200	OFFICE TRAILER OFFICE TRAILER PARKING AREA	G-13 G-12 G-13
1	C-412-T03 C-412-T04 C-412-T05	OFFICE TRAILER OFFICE TRAILER OFFICE TRAILER	G-10 G-10 G-10	C-616-P C-616-Q C-616-Sump		G-7 G-9 G-7	C-746-H3 C-746-H4 C-746-K	PEM STORAGE SLAB NICKEL INGOT STORAGE PAD SANITARY LANDFILL	F-9 F-7 D-11	C-1200-T08 C-1210 C-1212	OFFICE TRAILER VEHICLE BRIDGE WEST PARKING AREA	G-13 G-13 G-12
00	C-412-T06 C-412-T07 C-412-T08	OFFICE TRAILER SHOWER & CHANGE TRAILER OFFICE TRAILER	G-10 G-10 G-10	C-617-A C-617-B C-617-C	EFFLUENT CONTROL STATION EFFLUENT CONTROL LAGOON WETLAND & POND for OUTFALL 013	J-10 J-10 J-13	C-746-L C-746-N C-746-P	TRACTOR STORAGE SHED PAD SCRAP METAL YARD (EAST)	I-3 F-7 E-7	C-1215 C-1220 C-1220-M	VEHICLE ACCESS HOUSE "A" VEHICLE ACCESS HOUSE "B" MAC PORTAL ACCESS	G-13 G-12 G-12
2	C-412-T09 C-412-T10 C-412-T11A	OFFICE TRAILER OFFICE TRAILER SHOWER & CHANGE TRAILER	G-10 G-10 G-10	C-620 C-631-1 C-631-2	AIR COMPRESSOR ROOM PUMP HOUSE COOLING TOWER	I-10 I-9 I-9	C-746-P C-746-P1 C-746-P-T01 C-746-P-T03	SCRAP METAL YARD (WEST) SCRAP METAL TRAILER SCRAP METAL TRAILER	E-7 E-7 E-7 E-7	C-1300 C-1300-T01 C-1305	CONVERSION BUILDING CONVERSION BUILDING TRAILER HF STORAGE TANK AREA	G-12 G-12 G-12
	C-412-T12 C-412-T13 C-412-T14	SHOWER & CHANGE TRAILER OFFICE TRAILER OFFICE TRAILER	G-10 G-10 G-10	C-631-3 C-631-4 C-631-5	PUMP HOUSE (FIREWATER) BLENDING PUMP HOUSE BLENDING COOLING TOWER (WEST)	I-9 H-9 H-9	C-746-P -T04-A C-746-P-T05	SCRAP METAL TRAILER SCRAP METAL TRAILER SCRAP METAL TRAILER	E-7 E-7 F-7	C-1305A C-1305B C-1310	HF TANKER CAR CONTAINMENT PIT HF AREA CHANGE HOUSE NITROGEN SUPPLY SYSTEM AREA	G-12 G-12 G-12
00	C-415 C-416 C-416-T01	FEED PLANT STORAGE BUILDING EQUIPMENT CLEANING PAD SEALAND TRAILER	H-9 I-9 I-9	C-631-6 C-632-B	BLENDING COOLING TOWER (EAST) H2SO4 STORAGE TANK DIKE (TANK REMOVED)	I-9 H-9	C-746-Q C-746-Q1	HAZARDOUS & LLW STORAGE FACILITY HIGH ASSAY WASTE STORAGE BUILDING	I-12 I-12	C-1320 C-1330 C-1330B	KOH REGENERATION BUILDING HYDROGEN SUPPLY AREA HYDROGEN GENERATION	G-13 G-12 G-12
3	C-417 C-531-1	EQUIPMENT CLEANING PAD /STAGING AREA SWITCH HOUSE	I-9 I-9 J-10	C-633-1 C-633-2A C-633-2B	PUMP HOUSE COOLING TOWER (SOUTH) COOLING TOWER (NORTH)	J-12 J-12 J-12	C-746-R C-746-S C-746-S1	ORGANIC WASTE STORAGE AREA NEW SANITARY LANDFILL AREA LANDFILL SERVICE BUILDING	H-12 I-4 I-3	C-1604 C-1605	SYSTEM-SOUTH Main Fire Water System Backflow Preventer Building SERVICE WATER PUMP HOUSE	G-12 G-12
	C-531-2 C-531-3A C-531-3B	SWITCHYARD FIRE VALVE HOUSE NO. 1 FIRE VALVE HOUSE NO. 2	J-10 J-10 J-10	C-633-3 C-633-4 C-633-5	BLENDING PUMP HOUSE BLENDING COOLING TOWER (NORTH) BLENDING COOLING TOWER (SOUTH)	J-13 J-12 J-12	C-746-S2 C-746-S3 C-746-S4	SHED SHED SHED	I-3 I-3 I-3	C-1700 C-1745A	WAREHOUSE / MAINTENANCE BUILDING FULL CYLINDER STAGING AREA	G-12 G-13 G-13
00	C-532 C-533-1 C-533-2	RELAY HOUSE SWITCH HOUSE SWITCHYARD	I-10 J-11 J-11	C-633-6 C-635-1 C-635-2	SAND FILTER BUILDING BLENDING PUMP HOUSE and PIPING COOLING TOWER	J-11 G-8 G-8	C-746-T C-746-U C-746-U1	INDUSTRIAL LANDFILL LANDFILL LEACHATE OFFICE BUILDING	I-4 I&J-1&2 H-3	C-1745B C-1745C C-1900	EMPTY CYLINDER STAGING AREA OXIDE CYLINDER STAGING AREA DUF6 RAILROAD SPUR	G-12 G-12 E-13
4	C-533-3A C-533-3B C-533-3C	FIRE VALVE HOUSE NO. 1 FIRE VALVE HOUSE NO. 2 FIRE VALVE HOUSE NO. 3	J-11 J-11 J-11 J-11	C-635-3 C-635-4 C-635-5	BLENDING PUMP HOUSE BLENDING COOLING TOWER (NORTH) BLENDING COOLING TOWER (SOUTH)	G-8 G-8 G-8	C-746-U2 C-746-U3 C-746 -U4 to -U9	LANDFILL EQUIPMENT BUILDING LEACHATE FACILITY SEALAND STORAGE CONTAINERS	H-3 I-2 I-3	C-1910 C-1920 C-1930	SE RR BRIDGE SW RR BRIDGE BAYOU CREEK DUF6 RR BRIDGE	G-13 G-13 E-13
00	C-533-3D C-535-1 C-535-2	FIRE VALVE HOUSE NO. 4 SWITCH HOUSE SWITCHYARD	J-11 H-7 H-7	C-635-6 C-637-1	PROCESS WASTE HEAT UTILIZATION PUMP HOUSE PUMP HOUSE COOLING TOWER (SOUTH)	G-8 J-8	C-746-U10 C-746-U11 C-746-U12	STORAGE BUILDING STORAGE BUILDING STORAGE BUILDING	I-3 I-3 H-3	OUTFALL FACILIT	KPDES OUTFALLS	
	C-535-3A C-535-3B C-535-4	FIRE VALVE HOUSE NO. 1 FIRE VALVE HOUSE NO. 2 TEST SHOP (MAINTENANCE OFFICE)	H-7 H-7 H-7	C-637-2A C-637-2B C-637-3	COOLING TOWER (NORTH) BLENDING PUMP HOUSE	J-8 J-8 J-7	C-746-U13 C-746-U-T14 C-746-U15	STORM SHELTER TRAILER, SHOWER LEACHATE TREATMENT FACILITY	I-2 H-3 I-2	001 C-375- 002 C-375- 004 C-375-	W9 OIL CONTROL DAM (KPDES OUTFALL 001 E2 OIL CONTROL DAM (KPDES OUTFALL 002	2) K-9
5	C-536 C-537-1 C-537-2	RELAY HOUSE SWITCH HOUSE SWITCHYARD	H-7 I-7 I-7	C-637-4 C-637-5 C-637-6	BLENDING COOLING TOWER (NORTH) BLENDING COOLING TOWER (SOUTH) SAND FILTER BUILDING	J-7 J-8 J-8	C-746-U-S C-746-V	LEACHATE STORAGE FACILITY TRUCK SCALE WASTE STAGING PAD	I-2 H-3 F-8	004 C-375- 006 C-375- 008 C-375- 009 C-375-	06 C-611 No. 2 LAGOON (KPDES OUTFALL 000 W7 OIL CONTROL DAM (KPDES OUTFALL 008	6) C-8 3) D-9
00	C-537-3A C-537-3B C-537-3C	FIRE VALVE HOUSE NO. 1 FIRE VALVE HOUSE NO. 2 FIRE VALVE HOUSE NO. 3	H-7 H-7 I-7	C-709 C-710 C-710-A	TECHNICAL SERVICES BUILDING GAS CYLINDER STORAGE BUILDING	G-10 G-10 G-10	C-746-X C-747	ELECTRICAL EQUIPMENT STORAGE BUILDNG BURIAL AREA (INACTIVE)	I-7 E-9	009 C-375- 010 C-375- 011 C-375- 012 C-375-	E3 OIL CONTROL DAM (KPDES OUTFALL 010 E4 OIL CONTROL DAM (KPDES OUTFALL 011) K-10) K-10
	C-537-3D C-537-4 C-540-A	FIRE VALVE HOUSE NO. 4 TEST SHOP OIL PUMP HOUSE	I-7 I-7 J-10	C-711 C-712 C-720	ACID NEUTRALIZATION PIT MAINTENANCE & STORES BUILDING	G-10 G-10 F-10	C-747-A C-747-A-T01 C-747-B	BURIAL AREA (INACTIVE) HP ACCESS TRAILER BURIAL AREA (INACTIVE)	E-7 E-7 E-7	013 C-375- 015 C-375-	E6 PLANT SURFACE RUNOFF (KPDES OUTFALL W8 OIL CONTROL DAM (KPDES OUTFALL 015	013) K-13 5) D-9
6	C-540-A C-540-B C-540-C C-540-D	OIL STORAGE TANK (NORTHWEST) OIL STORAGE TANK (SOUTHWEST) OIL STORAGE TANK (NORTHEAST)	I-11 I-11 J-11	C-720 C-720-A C-720-B	COMPRESSOR SHOP MACHINE SHOP ADDITION	G-10 F-10 F-10	C-747-C C-747-D C-747-E	OIL LANDFARM AREA PAD PAD	E-9 F-9 F-9	017 C-375- 018 C-375-	 PLANT SURFACE RUNOFF FLUME (KPDES OUTF. PLANT SURFACE RUNOFF FLUME (KPDES OUTF. LANDFILL STORM WATER RUNOFF (KPDES OUTF. PLANT OUPFACE RUNOFF (KPDES OUTF. 	ALL 017) G-13 ALL 018) I-3
00	C-540-E C-541-A C-541-B	OIL STORAGE TANK (SOUTHEAST) OIL PUMP HOUSE OIL STORAGE TANK (NORTHWEST)	J-11 H-7 H-7	C-720-C C-720-C1 C-720-D	PAINT SHOP TRANSFORMER BUILDING	F-10 F-10 F-10	C-747-T07 C-748-A C-748-B	TRAILER KOW DISPOSAL AREA (INACTIVE) BURIAL AREA (INACTIVE)	F-9 D-11 E-9	019 C-375- 020 C-375-	20 TREATED LEACHATE RUNOFF (KPDES OUTFAL	
7	C-541-D C-541-D C-541-E	OIL STORAGE TANK (NORTHWEST) OIL STORAGE TANK (NORTHEAST) OIL STORAGE TANK (SOUTHEAST)	H-7 H-7 H-7 H-7	C-720-E C-720-G C-720-H	CHANGE HOUSE ADDITION WAREHOUSE WAREHOUSE	F-10 F-10 F-10	C-749 C-750	URANIUM SCRAP BURIAL YARD (INACTIVE) GARAGE BUILDING	E-8 G-10		PGDP Site Operational Responsibilities	
	C-600 C-600-A	STEAM PLANT C-600 STEAM PKG BOILERS - PB-01 thru PB-05	G-9 G-9	C-720-J C-720-K C-720-L	INSTRUMENT SHOP ADDITION LIQUID OXYGEN FACILITY TANK	G-10 G-10 G-10	C-750 C-750 C-752	ALCOHOL TANK - ABOVE GROUND PROPANE TANKS - NW of C-750 WASTE HOLDING PAD	G-10 G-10 G-8		DEACTIVATION & REMEDIATION CONTRACT	TOR
000	C-600-1 C-601	NEW COOLING TOWER NEXT TO C-604 NITROGEN GENERATOR	G-9 F-9	C-720-M C-720-M-T01 C-720-M-T02	COMPUTER MAINTENANCE TRAILER COMPUTER MAINTENANCE TRAILER	G-10 G-10 G-10	C-752-A C-752-A-ENC C-752-A-T10	STORAGE FACILITY WASTE CONTAINMENT ENCLOSURE WASTE OPERATIONS OFFICE TRAILER	F-8 F-8 F-8		DOE BOUNDARY (INFRASTRUCTURE - GROUNDS)	
8	C-601-A	BUILDING ADDITION STEAM PLANT FUEL -STORAGE TANK (CENTER) STEAM PLANT FUEL	G-9	C-720-N1 C-720-R C-720-S	MASS SPECTROMETER REPAIR TRAILER	B-18 F-10 G-10	C-752-B C-752-B-T01	OFFICE TRAILER FUELING STATION FUELING STATION TRAILER OFFSITE DECONTAMINATION FACILITY	E-11 E-11 E-11		DUF6 CONTRACTOR DEMOLISHED, SLAB or GRAVEL ONLY	
000	C-601-B C-601-C	-STORAGE TANK (SOUTH) STEAM PLANT FUEL OIL PUMP HOUSE	G-9 G-9	C-720-S C-720-U C-721 C-722		G-10 G-10 F-10 F-10	C-752-C -T01-T08 C-753-A	SEALAND STORAGE TRAILERS TSCA STORAGE FACILITY	E-11 G-8	A1-	▲49A GATE SYMBOL & NUMBER A2 PUBLIC WARNING SYSTEM SIRENS DNE AIR MONITORING STATIONS	
	C-602 C-603-E C-603-F	COAL STORAGE YARD NITROGEN STORAGE TANK (EAST) NITROGEN STORAGE TANK (CENTER)	F-9 F-9 F-9	C-724-A C-724-B C-724-C	CARPENTER SHOP ANNEX CARPENTER SHOP	F-10 F-10 F-10 F-10	C-754 C-754-A	LOW LEVEL WASTE STORAGE WASTE MANAGEMENT STAGING AREA	H-9 H-9	 PA-	NEW LIMITED AREA FENCE 05 (1) PUBLIC ADDRESS SPEAKERS/POLES	
	C-603-G C-604 C-604-A	NITROGEN STORAGE TANK (WEST) UTILITIES MAINTENANCE BUILDING UTILITIES STORAGE BUILDING	F-9 G-9 G-9	C-724-C C-724-D C-725 C-726	LUMBER STORAGE BUILDING PAINT SHOP SANDBLAST BUILDING	F-10 F-9 F-9 G-9	C-754-B C-755 C-755-T01 C-755-T02	LOW LEVEL WASTE STORAGE C-755 TRAILER COMPLEX OFFICE TRAILER OFFICE TRAILER	I-9 I-9 K-9	RE	D 5/11/2018 QUARTERLY UPDATE SRD JD MD v. DATE DESCRIPTION DRAWN BY TECHNICAL REVIEW QUALITY REVIEW U.S. DEPARTMENT OF ENERGY	
	C-605 C-606	SUBSTATION BUILDING COAL CRUSHER BUILDING	G-9 G-9	C-720 C-727		H-10	C-755-T02 C-755-T03	OFFICE TRAILER OFFICE TRAILER	K-9 J-9		PADUCAH GASEOUS DIFFUSION PLANT SITE MAP cah, KY Drawn by S.R. Durbin, Pro2Serve REV. NO.	
											PAD-P2S-15-GIS-0001 10	





			(C-400 COMPLEX
Operable Unit	Subp	roject	SWMU No.	Description
	C-400 D&D		Other	C-400 Building [building foundation (i.e., slab) will remain in place]
			11	C-400 TCE Leak Site
<i></i>			40	C-403 Neutralization Tank slab and underlying soils
C-400	C-400) Final	47	C-400 Technetium Storage Tank Area
Complex OU	Rem	nedial	98	C-400 Basement Sump
	Ac	tion	203	C-400 Discard Waste System slab and underlying soils
			480	C-402 Lime House building slab and underlying soils
			533	TCE Spill Site from TCE Unloading Operations at C-400
	1		(GROUNDWATER
	C-400	Interim	11	C-400 TCE Leak Site
		nedial tion	533	TCE Spill Site from TCE Unloading Operations at C-400
	AU	tion	1	C-747-C Oil Land Farm
	Southwest		211 A	C-720 TCE Spill Site Northeast
	Plume Sources		211 A 211 B	C-720 TCE Spill Site Southeast
GWOU			201	Northwest Groundwater Plume
0,000	Dissolved- Phase Plumes		201	Northeast Groundwater Plume
			202	Southwest Groundwater Plume
	Pote	ential	NA	This operable unit is being reserved for remaining sources to
		tional	1 12 1	groundwater contamination that may be identified in the future
		dwater		Bround water containing too had hind in the fature
		irces		
	1		S	URFACE WATER
			58	NSDD (Outside) (includes KPDES 003)
			60	C-375-E2 Effluent Ditch (KPDES 002) ¹
		-	61	C-375-E5 Effluent Ditch (KPDES 013) ¹
	\sim		62	C-375-S6 SW Ditch (KPDES 009) ¹
	W		63	C-375-W7 Oil Skimmer Ditch (KPDES 008 and KPDES 004)
	υC	Re	66	C-375-E3 Effluent Ditch (KPDES 010)
	Re	mo	67	C-375-E4 Effluent Ditch (C-340 Ditch) (KPDES 011)
SWOU	SWOU Remedial Action	val	68	C-375-W8 Effluent Ditch (KPDES 015)
		Removal Action	69	C-375-W9 Effluent Ditch (KPDES 001)
		tio	92	Fill Area for Dirt from the C-420 PCB Spill Site
	ctic	р	97	C-601 Diesel Spill
	nc		102B	Plant Storm Sewer associated with C-333-A, C-337-A, C-340, C-535, and C-537 ¹
			168	KPDES Outfall Ditch 012 ¹
	1		100	

Table A.1. Solid Waste Management Units/Areas of Concern by Operable Unit*

Internal Plant Drainage Ditches (includes KPDES 016)²

526

¹ The results of the Surface Water Operable Unit (SWOU) (On-Site) Site Investigation determined that there were no unacceptable levels of risk to current and anticipated future receptors that warranted inclusion of Solid Waste Management Unit (SWMU) 60 (Outfall 002), SWMU 168 (Outfall 012), or SWMU 102 [Paducah Gaseous Diffusion Plant (PGDP) storm sewer systems associated with C-333-A, C-337-A, C-340, C-535, and C-537]. As a result, no action will be taken for these SWMUs as originally planned under the SWOU removal action. These SWMUs will be evaluated further as part of the SWOU remedial action. It also should be noted that during development of the Sampling and Analysis Plan (SAP) for SWOU (On-Site) Removal Action, Outfall 009 and Outfall 013 were evaluated. This assessment of the outfalls, which included a review of historical data, indicated that Outfall 009 and Outfall 013 did not require an early action, and further assessment of Outfall 009 and Outfall 013 would be addressed during the Comprehensive Site Operable Unit (CSOU). Based upon current site strategy, Outfall 009 and Outfall 013 also will be addressed as part of the SWOU remedial action.

² Kentucky Pollutant Discharge Elimination System (KPDES) Outfall 016, in its entirety, will be addressed as part of the SWOU Remedial Investigation.

		SURFA	CE WATER (CONTINUED)
Operable Unit	Subproject	SWMU No.	Description
		64	Little Bayou Creek
		65	Bayou Creek
		93	Concrete Disposal Area East of Plant Security Area
		105	Concrete Rubble Pile (3)
		106	Concrete Rubble Pile (4)
	SW	107	Concrete Rubble Pile (5)
	SWOU Remedial Action	108	Concrete Rubble Pile (6)
		109	Concrete Rubble Pile (7)
GWOU	len	113	Concrete Rubble Pile (11)
SWOU	ned	129	Concrete Rubble Pile (27)
	ial	175	Concrete Rubble Pile (28)
	Ac	185	C-611-4 Horseshoe Lagoon (includes KPDES 014)
	tion	199	Bayou Creek Monitoring Station
		205	Eastern Portion of Yellow Water Line
		549	Dirt/Concrete Rubble Pile near Outfall 008
		550	Concrete Culvert Sections Located on the West Bank of the
			Ditch Leading to Outfall 001
		Others	Outfalls 017, 018, 019/020, and 526 and associated ditches
			LAGOONS
	D	17	C-616-E Sludge Lagoon
	Process Lagoons	18	C-616-F Full-Flow Lagoon
т		171	C-617-B Lagoon (formerly identified as C-617-A)
Lagoons	Water	21	C-611-W Sludge Lagoon
OU	Treatment	22	C-611-Y Overflow Lagoon (includes KPDES 006)
	System	23	C-611-V Lagoon (includes KPDES 005)
	Lagoons		
			BURIAL GROUNDS
		2	C-749 Uranium Burial Ground
		3	C-404 Low-Level Radioactive Waste Burial Ground
		4	C-747 Contaminated Burial Ground
	BGOU	5	C-746-F Classified Burial Ground
	Remedial	6	C-747-B Burial Area
	(10	7	C-747-A Burial Ground
BGOU	SWMUs)	9	C-746-S Residential Landfill
		10	C-746-T Inert Landfill
		30	C-747-A Burn Area
		145	Residential/Inert Landfill Borrow Area (P-Landfill)
	Additional	472	C-746-B Pad
	Burial Grounds	520	Scrap Material West of C-746-A

* Information is taken from the Site Management Plan, DOE/LX/07-2418&D2, April 2018 A-10

			SOILS
Operable Unit	Subproject	SWMU No.	Description
		1	C-747-C Oil Land Farm
		13	C-746-P Clean Scrap Yard ³
		14	C-746-E Contaminated Scrap Yard
		15	C-746-C Scrap Yard ³
		19	C-410-B HF Neutralization Lagoon
		26	C-400 to C-404 Underground Transfer Line ³
		56	C-540-A PCB Waste Staging Area ^{3, 4}
		57	C-541-A PCB Waste Staging Area ⁴
		76	C-632-B Sulfuric Acid Storage Tank
		77	C-634-B Sulfuric Acid Storage Tank ^{3, 5}
		80	C-540-A PCB Spill Site ³
		81	C-541-A PCB Spill Site
		99 B	C-745 Kellogg Bldg. Site—Septic Tank/Leach Field
		138	C-100 Southside Berm
		153	C-331 PCB Soil Contamination (West)
		156	C-310 PCB Soil Contamination (West Side)
		158	Chilled-Water System Leak Site
		160	C-745 Cylinder Yard Spoils (PCB Soils)
		163	C-304 Bldg./HVAC Piping System (Soil Backfill)
	Soils	165	C-616-L Pipeline & Vault Soil Contamination
Soils OU	Remedial	169	C-410-E HF Vent Surge Protection Tank
	Remediai	170	C-729 Acetylene Bldg. Drain Pits
		180	Outdoor Firing Range (WKWMA)
		181	Outdoor Firing Range (PGDP)
		194	McGraw Construction Facilities (Southside)
		195	Curlee Road Contaminated Soil Mounds
		196	C-746-A Septic System
		200	Soil Contamination South of TSCA Waste Storage Facility
	Γ	204	Dykes Road Historical Staging Area ³
	Γ	211 A	C-720 TCE Spill Site Northeast ³
	Γ	212	C-745-A Radiological Contamination Area
		213	OS-02
		214	OS-03
		215	OS-04
	Γ	216	OS-05
		217	OS-06
		219	OS-08
		221	OS-10
		222	OS-11
		224	OS-13 ³
		225A	OS-14 ³

³ These SWMUs/areas of concern (AOCs) will be evaluated further under a Soils OU RI 2 and addressed by a subsequent Soils

OU feasibility study. ⁴ SWMUs 56 and 57 are located within, and will be addressed as part of, SWMUs 80 and 81, respectively. ⁵ This SWMU was evaluated as part of the Soils Operable Unit. The soils and underlying slabs associated with this SWMU will be addressed under the Soils and Slabs OU as part of post-GDP shutdown activities.

		SO	ILS (CONTINUED)
Operable Unit	Subproject	SWMU No.	Description
•	1 9	225 B	Contaminated Soil Area near C-533-1 DMSA OS-14 ³
		227	OS-16
		228	OS-17
		229	OS-18 ³
		486	Rubble Pile WKWMA (approximately 116 ft off roadside)
		487	Rubble Pile WKWMA (approximately 483 ft off roadside)
		488	PCB Contamination Area by the C-410 Trailer Complex
		489	Septic Tank North of C-710 Laboratory
		492	Contaminated Soil Area Near Outfall 010
		493	Concrete Rubble Piles Near Outfall 001
		517	Rubble and Debris Erosion Control Fill Area
		518	Field South of C-746-P1 Clean Scrap Yard
Soils OU	Soils	520	Scrap Material West of C-746-A
(Continued)	Remedial (Continued)	531	Aluminum Slag Reacting Area (C-746-H4) near the C-746-A Facility
		541	Contaminated Soil Area South of Outfall 011
		561	Soil Pile I
		562	Soil Piles C, D, E, F, G, H, J, K, and P in subunit 1 north of Soil
			Pile I on the west bank of Little Bayou Creek
		563	Soil Piles 20, CC, and BW in subunit 4 north of outfall 012 west
			of Little Bayou Creek
		564	Soil Pile AT in subunit 5 that consists of three soil areas on the
			east side of the North-South Diversion Ditch north of the P-, S-,
			and T-Landfills
		565	Rubble Area KY-19 (along Bayou Creek north of C-611 Water
		5(7	Treatment Plant) ³
		567	Soil Pile K013 near Outfall 013, West of Little Bayou Creek
		1	OILS AND SLABS
		16	C-746-D Classified Scrap Yard
		20	C-410-E Emergency Holding Pond slab and underlying soils
		27	C-722 Acid Neutralization Tank
		28	C-712 Laboratory Equalization Tank slab and underlying soils
		31	C-720 Compressor Pit Water Storage Tank slab and underlying soils
		22	C-728 Clean Waste Oil Tanks slab and underlying soils
Soils and Slabs		32	
OU		33	C-728 Motor Cleaning Facility slab and underlying soils
(Continued)		41	C-615 Sewage Treatment Plant slab and underlying soils C-410-C Neutralization Tank slab and underlying soils
		41	C-616 Chromate Reduction Facility slab and underlying soils
		55	C-405 Incinerator building slab and underlying soils
		70	C-333-A Vaporizer slab and underlying soils
		70	C-337-A Vaporizer slab and underlying soils
		74	C-340 PCB Transformer Spill Site
		74	C-633 PCB Spill Site
		13	U-000 T CD opin one

* Information is taken from the Site Management Plan, DOE/LX/07-2418&D2, April 2018 A-12

		SOILS A	ND SLABS (CONTINUED)
Operable Unit	Subproject	SWMU No.	Description
	1 0	77	C-634-B-Sulfuric Acid Storage Tank slab and underlying soils
		78	C-420 PCB Spill Site
		79	C-611 PCB Spill Site
		82	C-531 Electric Switchyard slab and underlying soils
		83	C-533 Electric Switchyard slab and underlying soils
		84	C-535 Electric Switchyard slab and underlying soils
		85	C-537 Electric Switchyard slab and underlying soils
		86	C-631 Pumphouse and Cooling Tower slab and underlying soils
		87	C-633 Pumphouse and Cooling Tower slab and underlying soils
		88	C-635 Pumphouse and Cooling Tower slab and underlying soils
		89	C-637 Pumphouse and Cooling Tower slab and underlying soils
		99 A	C-745 Kellogg Bldg. Site-Cylinder Yard
		135	C-333 PCB Soil Contamination (North Side)
		137	C-746-A Inactive PCB Transformer Sump Area ⁶
		154	C-331 PCB Soil Contamination (Southeast)
		155	C-333 PCB Soil Contamination (West)
		159	C-746-H3 Storage Pad slab and underlying soils
		161	C-743-T-01 Trailer Site (Soil Backfill)
		162	C-617-A Sanitary Water Line (Soil Backfill)
		166	C-100 Trailer Complex Soil Contamination (East Side)
Soils and Slabs		167	C-720 White Room Sump slab and underlying soils
OU		172	C-726 Sandblasting Facility slab and underlying soils
(Continued)		176	C-331 RCW Leak Northwest Side
		177	C-331 RCW Leak East Side
		178	C-724-A Paint Spray Booth slab and underlying soils
		179	Plant Sanitary Sewer System
		192	C-710 Acid Interceptor Pit slab and underlying soils
		198	C-410-D Area Soil Contamination slab and underlying soils
		209	C-720 Compressor Shop Pit Sump slab and underlying soils
		211 B	C-720 TCE Spill Site Southeast
		218	OS-07 slab and underlying soils
		220	OS-09 slab and underlying soils
		223	OS-12 slab and underlying soils
		226	OS-15
		463	C-746-A East End Smelter slab and underlying soils
		464	C-746-A West End Smelter building slab and underlying soils
		469	C-745-J Yard
		470	C-746-V Yard
		474	West of Vortec Site
		477	C-340 Metals Plant building slab and underlying soils
		478	C-410/420 Feed Plant building slab and underlying soils
		482	C-415 Feed Plant Storage Building slab and underlying soils
		483	Nitrogen Generating Facilities slab and underlying soils

⁶ SWMU 137 was evaluated as part of the American Recovery and Reinvestment Act and the Soils OU. SWMU 137 will be addressed as part of Soils and Slabs OU.

	SOILS AND SLABS (CONTINUED)					
Operable Unit	Operable Unit Subproject SWMU No. Description					
		498	C-410/420 Sump at Column D & E-1&2 slab and underlying soils			
		499	C-410/420 Sump at Column H-9&10 slab and underlying soils			
		500	C-410/420 Sump at Column U-10&11 slab and underlying soils			
		501	C-410/420 UF ₆ Scale Pit Sumps A&B slab and underlying soils			
		502	C-410/420 Sump at Column U-9 slab and underlying soils			
		503	C-410/420 Sump at Column G-1 slab and underlying soils			
		504	C-410/420 Sump at Column L-10 slab and underlying soils			
		505	C-410/420 Sump at Column A-3N slab and underlying soils			
		506	C-410/420 Sump at Column Wa-9 slab and underlying soils			
		507	C-410/420 Condensate Tank Pit slab and underlying soils			
Soils and Slabs		508	C-410/420 Settling Basin slab and underlying soils			
OU		509	C-410/420 Drain pit slab and underlying soils			
(Continued)		510	C-410/420 Sump at Column P&Q-2 slab and underlying soils			
		511	C-410/420 Sump at Column Q&R-2 slab and underlying soils			
		512	C-410/420 Sump at Column R-2 slab and underlying soils			
		513	C-411 Cell Maintenance Room Sump slab and underlying soils			
		522	C-340 Work Pit at Ground Floor Level (B-7–B-9) slab and			
			underlying soils			
		523	C-340 Metals Plant Pit at Ground Floor (F-6 to F-11) slab and			
		52.4	underlying soils			
		524	C-340 Pickling System Sump (B-10 to B-11) slab and			
		529	underlying soils C-340 Powder Plant Sump at Ground Floor Level slab and			
		529	underlying soils			
	DEC	ONTAMINAT	ION AND DECOMMISSIONING			
			SWMUs/AOCs or facilities may include multiple smaller			
			re detailed listing is included in the following table entitled			
		33	C-728 Motor Cleaning Facility			
		38	C-615 Sewage Treatment Plant			
		42	C-616 Chromate Reduction Facility			
		70	C-333-A Vaporizer			
		71	C-337-A Vaporizer			
		82	C-531 Electric Switchyard			
		83	C-533 Electric Switchyard			
	Damainina	84	C-535 Electric Switchyard			
Facility D&D OU	Remaining D&D	85	C-537 Electric Switchyard			
	D&D	86	C-631 Pumphouse and Cooling Tower			
		87	C-633 Pumphouse and Cooling Tower			
		88	C-635 Pumphouse and Cooling Tower			
		89	C-637 Pumphouse and Cooling Tower			
		172	C-726 Sandblasting Facility			
		178	C-724-A Paint Spray Booth			
		482	C-415 Feed Plant Storage Building			
		Other	C-310, C-310-A, C-315, C-331, C-333, C-333-A. C-335, C-337,			
		Buildings	C-337-A, C-409, C-600, C-709, C-710, C-720			
			Process Building tie-lines and bridges will be included with the appropriate process building.			
			appropriate process bundling.			

DUF₆ FOOTPRINT UNDERLYING SOILS				
	164	KPDES Outfall Ditch 017 Flume - Soil Backfill		
DUF ₆ Footprint Underlying Soils	183	McGraw UST		
Olderlying Solis OU	193	McGraw Construction Facilities (Southside Cylinder Yards)		
00	194	McGraw Construction Facilities (Southside)		
	FINAL COMPREH	ENSIVE SITE OPERABLE UNIT		
	SWMU No.	Description		
	8	C-746-K Inactive Sanitary Landfill		
CSOU ^{7,8}	59	NSDD (Inside)		
	91	UF ₆ Cylinder Drop Test Area		
	100	Fire Training Area		

⁷ The FFA, as currently written, contemplates multiple CSOUs, consisting of those associated with integrator units (i.e., groundwater, surface water), and a final CSOU completed after issuance of all final RODs for the site. The FFA parties acknowledge that the scope description is intended to reflect a single CSOU to address all media, and a future FFA modification will be conducted to resolve any inconsistencies between the FFA and Site Management Plan strategy.

⁸ Historically, once an action has been completed for a particular SWMU whereby no additional active response actions are expected, such SWMUs have been placed in the CSOU for further evaluation; however, the FFA parties recognized the need to reach consensus on the criteria for assigning units to the CSOU. As a result, placement of SWMUs 8, 59, 91, and 100 in the CSOU is provisional pending the FFA parties reaching consensus on such criteria.

Table A.1. Solid Waste Management Units/Areas of Concern by Operable Unit* (Continued)

	PERMITTED			
	SWMU No.	Description		
	3	C-404 Low-Level Radioactive Waste Burial Ground ⁹		
	9	C-746-S Residential Landfill		
	10	C-746-T Inert Landfill		
Permitted	44	C-733 Hazardous Waste Storage Area		
	46A	C-746-Q Hazardous and Low-Level Mixed Waste Storage		
		Facility		
	207	C-752-A ER Waste Storage Bldg.		
	208	C-746-U Solid Waste Contained Landfill		

⁹ SWMU 3 was issued only a post-closure permit, was not permitted for construction and operation, and was not an engineered hazardous waste landfill.

^{*} Information is taken from the Site Management Plan, DOE/LX/07-2418&D2, April 2018 A-16

	NO FURTHER ACTION	
SWMU No.	Description	NFA Approval By
12	C-747-A UF ₄ Drum Yard	FFA Managers Agreement– November 17, 2011; FFA Managers Meeting, 4/12/2012
24	C-750-D UST	KDWM (UST Branch) 11/23/1999
25	C-750 1,000-gal Waste Oil Tank (UST)	EPA HSWA Class 1 Permit Mod 3/17/1993—Regulated by RCRA Permit; KDWM (UST Branch) 6/20/1994
29	C-746-B TRU Storage Area	EPA HSWA Class 1 Permit Mod 3/17/1993
34	C-746-M PCB Waste Storage Area	EPA HSWA Class 1 Permit Mod 3/17/1993
35	C-337 PCB Waste Storage Area	EPA HSWA Class 1 Permit Mod 3/17/1993
36	C-337 PCB Waste Staging Area	EPA HSWA Class 1 Permit Mod 3/17/1993
37	C-333 PCB Waste Staging Area	EPA HSWA Class 1 Permit Mod 3/17/1993
39	C-746-B PCB Waste Storage Area	EPA HSWA Class 1 Permit Mod 3/17/1993
43	C-746-B Waste Chemical Storage Area	EPA HSWA Class 1 Permit Mod 3/17/1993; Closed after 1993
45	C-746-R Waste Solvent Storage Area	EPA HSWA Class 1 Permit Mod 3/17/1993; Closed after 1993
46	C-409 Hazardous Waste Pilot Plant ¹⁰	EPA HSWA Class 1 Permit Mod 3/17/1993—Regulated by RCRA Permit; KDWM (Mod #13) 9/26/1997
48	Gold Dissolver Storage Tank (DMSA C400-03)	EPA HSWA Class 1 Permit Mod 3/17/1993; KDWM 7/8/2010
49	C-400-B Waste Solution Storage Tank	EPA HSWA Class 1 Permit Mod 3/17/1993—Regulated by RCRA Permit; KDWM 9/26/1997
50	C-400-C Nickel Stripper Evaporation Tank	EPA HSWA Class 1 Permit Mod 3/17/1993—Regulated by RCRA Permit; KDWM (Mod #13) 9/26/1997
51	C-400-D Lime Precipitation Tank	EPA HSWA Class 1 Permit Mod 3/17/1993—Regulated by RCRA Permit; KDWM (ROC) 8/8/1994
52	C-400 Waste Decontamination Solution Storage Tanks	EPA HSWA Class 1 Permit Mod 3/17/1993
53	C-400 NaOH Precipitation Unit	EPA HSWA Class 1 Permit Mod 3/17/1993
54	C-400 Degreaser Solvent Recovery Unit	EPA HSWA Class 1 Permit Mod 3/17/1993; KDWM 7/8/2010
72	C-200 Underground Gasoline Tanks	EPA HSWA Class 1 Permit Mod 3/17/1993; KDWM (UST C-200A; UST Branch) 11/23/1999

¹⁰ Radiological contamination associated with the sump in this unit will be addressed under the D&D program for the C-409 Stabilization Building.

SWMU No.	NO FURTHER ACTION (CONTINUED Description	NFA Approval By
73	C-710 Underground Gasoline Tanks	EPA HSWA Class 1 Permit Mod
73	C-710 Onderground Gasonne Taiks	3/17/1993; KDWM (UST C-200A;
		UST C-710; UST Branch) 2/19/2002
90	C-720 Petroleum Naphtha Pipe	KDWM 1/14/2015
96	C-333 Cooling Tower Scrap Wood Pile	EPA HSWA Class 1 Permit Mod
90	C-555 Cooling Tower Scrap wood The	3/17/1993
101	C-340 Hydraulic System	EPA and KDWM 4/2/2015
101 102A	Plant Storm Sewer—between the south side of the C-400 Building	EPA and KD with 4/2/2015 EPA and KY via SW Plume ROD
	and Outfall 008	3/16/2012; KDWM 1/14/2015
103	Concrete Rubble Pile (1)	EPA and KY via WAG 17 ROD 9/29/1997
104	Concrete Rubble Pile (2)	EPA and KY via WAG 17 ROD 9/29/1997
110	Concrete Rubble Pile (8)	EPA and KY via WAG 17 ROD 9/29/1997
111	Concrete Rubble Pile (9)	EPA and KY via WAG 17 ROD 9/29/1997
112	Concrete Rubble Pile (10)	EPA and KY via WAG 17 ROD 9/29/1997
114	Concrete Rubble Pile (12)	EPA and KY via WAG 17 ROD 9/29/1997
115	Concrete Rubble Pile (13)	EPA and KY via WAG 17 ROD 9/29/1997
116	Concrete Rubble Pile (14)	EPA and KY via WAG 17 ROD 9/29/1997
117	Concrete Rubble Pile (15)	EPA and KY via WAG 17 ROD 9/29/1997
118	Concrete Rubble Pile (16)	EPA and KY via WAG 17 ROD 9/29/1997
119	Concrete Rubble Pile (17)	EPA and KY via WAG 17 ROD 9/29/1997
120	Concrete Rubble Pile (18)	EPA and KY via WAG 17 ROD 9/29/1997
121	Concrete Rubble Pile (19)	EPA and KY via WAG 17 ROD 9/29/1997
122	Concrete Rubble Pile (20)	WAG 17 RI Work Plan
123	Concrete Rubble Pile (21)	EPA and KY via WAG 17 ROD 9/29/1997
124	Concrete Rubble Pile (22)	EPA and KY via WAG 17 ROD 9/29/1997
125	Concrete Rubble Pile (23)	EPA and KY via WAG 17 ROD 9/29/1997
126	Concrete Rubble Pile (24)	EPA and KY via WAG 17 ROD 9/29/1997
127	Concrete Rubble Pile (25)	EPA and KY via WAG 17 ROD 9/29/1997
128	Concrete Rubble Pile (26)	EPA and KY via WAG 17 ROD 9/29/1997
130	C-611 550-gal Gasoline UST	KDWM 12/6/1996 EPA and KY via WAG 1&7 ROD

SWMU No.	NO FURTHER ACTION (CONTINUED) WMU No. Description				
131	C-611 50-gal Gasoline UST	KDWM 12/6/1996 EPA and KY via WAG 1&7 ROD 8/10/1998			
132	C-611 2,000-gal Oil UST	KDWM 12/6/1996 EPA and KY via WAG 1&7 ROD 8/10/1998			
133	C-611 (unknown size) Grouted UST	KDWM 12/6/1996 EPA and KY via WAG 1&7 ROD 8/10/1998			
134	C-611 1,000-gal Diesel/Gasoline Tank	KDWM 12/6/1996 EPA and KY via WAG 1&7 ROD 8/10/1998			
136	C-740 TCE Spill Site	EPA and KY via WAG 1&7 ROD 8/10/1998			
139	C-746-A1 UST	KDWM 12/9/2005			
140	C-746-A2 UST	KDWM 12/19/1996			
141	C-720 Inactive TCE Degreaser	KDWM 8/11/1992; EPA HSWA Class 1 Permit Mod 3/17/1993— Regulated by RCRA Permit;			
142	C-750-A 10,000-gal Gasoline Tank (UST)	EPA HSWA Class 1 Permit Mod 3/17/1993—Regulated by RCRA Permit; KDWM 3/25/1999			
143	C-750-B 10,000-gal Diesel Tank (UST)	EPA HSWA Class 1 Permit Mod 3/17/1993; KDWM 3/25/1999			
144	C-746-A Hazardous and Mixed Waste Storage Facility	KDWM 10/10/2011			
146	Concrete Rubble Pile (40)	EPA and KY via WAG 17 ROD 9/29/1997			
147	Concrete Rubble Pile (41)	EPA and KY via WAG 17 ROD 9/29/1997			
148	Concrete Rubble Pile (42)	EPA and KY via WAG 17 ROD 9/29/1997			
149	Concrete Rubble Pile (43)	EPA and KY via WAG 17 ROD 9/29/1997			
150	Concrete Rubble Pile (44)	EPA and KY via WAG 17 ROD 9/29/1997			
151	Concrete Rubble Pile (45)	EPA and KY via WAG 17 ROD 9/29/1997			
152	Concrete Rubble Pile (46)	EPA and KY via WAG 17 ROD 9/29/1997			
173	C-746-A Trash-Sorting Facility	EPA HSWA Class 1 Permit Mod 3/17/1993; KDWM 12/18/1992			
174	C-745-K Low-Level Storage Area	EPA HSWA Class 1 Permit Mod 3/17/1993; KDWM 2/22/1993			
184	Concrete Rubble Pile (29)	EPA and KY via WAG 17 ROD 9/29/1997			
186	C-751 Fuel Facility	KDWM 10/20/1993			
187	C-611 Septic System	KDWM 10/20/1993			
188	C-633 Septic System	KDWM 10/20/1993			
189	C-637 Septic System	KDWM 10/20/1993			
190	C-337A Sewage Treatment Aeration Tank	KDWM 10/20/1993			
191	C-333-A Sewage Treatment Aeration Tank	KDWM 10/20/1993			

WMU No.	Description	NFA Approval By
197	Concrete Rubble Pile (30)	EPA and KY via WAG 17 ROD
206	C 752 A Tavia Substances Control Act Wests Stores Dldg	9/29/1997 KDWM 3/7/1997
208	C-753-A Toxic Substances Control Act Waste Storage Bldg. C-746-U Solid Waste Contained Landfill	KDWM 3/7/1997
360	C-535	KDWM 3///1997 KDWM 1/4/2006
		KDWM 8/28/2007
361	C-727–90 day	
362 363	G-310-04 G-331-03	KDWM 8/28/2007
		KDWM 6/29/2004
364	G-331-05	KDWM 6/29/2004
365	G-333-02	KDWM 5/12/2003
366	G-333-03	KDWM 5/12/2003
367	G-333-04	KDWM 5/12/2003
368	G-333-08	KDWM 6/29/2004
369	G-333-10	KDWM 5/12/2003
370	G-333-20	KDWM 5/12/2003
371	G-335-01	KDWM 1/4/2006
372	G-337-02	KDWM 9/11/2003
373	G-337-03	KDWM 9/11/2003
374	G-337-13	KDWM 9/11/2003
375	G-337-14	KDWM 9/11/2003
376	G-337-15	KDWM 9/11/2003
377	C-337-22	KDWM 1/4/2006
378	G-340-01	EPA and KDWM 4/02/2015
379	G-340-03	EPA and KDWM 4/02/2015
380	G-340-04	EPA and KDWM 4/02/2015
381	G-340-05	EPA and KDWM 4/02/2015
382	G-340-06	KDWM 8/28/2007
383	G-400-01	KDWM 5/12/2003
384	G-400-02	KDWM 5/12/2003
385	G-409-25	KDWM 5/12/2003
386	G-410-01	KDWM 8/28/2007
387	C-416-01	KDWM 8/28/2007
388	C-416 Decontamination Pad	KDWM 4/12/2004
389	G-533-01	KDWM 6/29/2004
390	G-535-02	KDWM 6/29/2004
391	G-537-01	KDWM 1/4/2006
392	G-540-A-01	KDWM 2/14/2006
393	G-540-A-1-02	KDWM 2/14/2006
394	G-541-A-01	KDWM 4/12/2004
<u>395</u> 396	G-600-01	KDWM 3/8/2007
	C-611-U-01	KDWM 3/8/2007
397	G-612-01	KDWM 3/8/2007
398 399	G-612-02 G-612-A-01	KDWM 3/8/2007 KDWM 3/8/2007
400	G-635-01	KDWM 3/8/2007 KDWM 3/8/2007
400 401	G-710	KDWM 3/8/2007 KDWM 1/4/2006
401 402	G-710-04	KDWM 1/4/2006 KDWM 9/11/2003
402 403	G-710-04 G-710-20	KDWM 9/11/2003 KDWM 1/4/2006
403	G-710-20 G-710-24	KDWM 1/4/2006 KDWM 9/11/2003
404 405	G-710-24 G-720-22	KDWM 9/11/2003 KDWM 2/14/2003
403	G-720-22 G-743-T-17-01	KDWM 2/14/2003 KDWM 6/29/2004
400	G-743-T-17-02	KDWM 3/8/2007

	NO FURTHER ACTION (C	CONTINUED)
SWMU No.	Description	NFA Approval By
408	G-745-B-01	KDWM 3/8/2007
409	G-745-T-01	KDWM 2/14/2006
410	G-746-G-01	KDWM 6/29/2004
411	G-746-G-1-01	KDWM 3/8/2007
412	G-746-G-2-01	KDWM 11/1/2004
413	G-746-G-3-01	KDWM 11/1/2004
414	G-746-F-01	KDWM 1/4/2006
415	G-746-S-01	KDWM 8/28/2007
416	G-746-X-01 (PCBs)	KDWM 3/8/2007
417	G-746-X-01 (Asbestos)	KDWM 3/8/2007
418	G-748-B-01	KDWM 6/29/2004
419	G-752-C-01	KDWM 8/28/2007
420	G-752-C-02	KDWM 3/8/2007
421	G-754-01	KDWM 1/4/2006
422	G-755-A-01	KDWM 1/28/2004
423	G-755-C-01	KDWM 1/28/2004
424	G-755-T-07-01	KDWM 1/28/2004
425	G-755-T-08	KDWM 1/28/2004
426	G-755-T-2-3-01	KDWM 1/28/2004
427	G-755-T-3-1-01	KDWM 1/28/2004
428	G-755-T-3-2-01	KDWM 1/28/2004
429	S-310-04	KDWM 8/28/2007
430	S-331-02	KDWM 1/4/2006
431	8-333-12	KDWM 5/12/2003
432	8-335-09	KDWM 11/23/2004
433	8-337-11	KDWM 9/11/2003
434	S-340-01	EPA and KY 4/2/2015
435	S-409-100	KDWM 5/12/2003
436	S-409-20	KDWM 5/12/2003
437	S-409-40	KDWM 5/12/2003
438	S-409-60	KDWM 5/12/2003
439	S-409-80	KDWM 5/12/2003
440	S-410-05	KDWM 8/28/2007
441	S-540-A-2-01	KDWM 6/29/2004
442	8-612-01	KDWM 2/14/2006
443	S-709-01	KDWM 6/29/2004
444	S-709-02	KDWM 6/29/2004
445	S-710-05	KDWM 2/14/2006
446	S-710-06	KDWM 9/11/2003
447	S-710-09	KDWM 1/4/2006
447	S-710-16	KDWM 1/4/2000 KDWM 9/11/2003
448	S-710-18	KDWM 9/11/2003 KDWM 9/11/2003
450		KDWM 1/4/2005
	S-710-32	
451	S-710-41	KDWM 9/11/2003
452	S-710-44	KDWM 1/4/2006
453	S-710-46	KDWM 9/11/2003
454	S-743-T-17-01	KDWM 2/14/2006
455	S-755-T-16-01	KDWM 1/28/2004
456	S-755-T-16-02	KDWM 1/28/2004
457	S-755-T-16-03	KDWM 1/28/2004
458	S-755-T-2-3-01	KDWM 1/28/2004
459	S-755-T-3-1-01	KDWM 1/28/2004

WMU No.	Description	NFA Approval By
460	S-755-T-3-2-01	KDWM 1/28/2004
461	S-755-T-3-2-02	KDWM 1/28/2004
462	S-755-T-3-2-03	KDWM 1/28/2004
465	Yard Rubble Pile and Crushate Storage Area (G-Yard)	KDWM 10/13/2009
466	South of Dyke Road, Pond Area	KDWM 8/17/2009
467	Concrete Cylinder Holders Storage Area on Western Kentucky	KDWM 8/17/2009
460	Wildlife Management Area	
468	Area Northwest of Outfall 015	KDWM 2/14/2006
471	Outside C-746-B South Storage Area	KDWM 8/17/2009
473	C-746-B Pad, West	KDWM 8/28/2007
475	C-745-G5-01 (Paint Enclosure)	KDWM 2/14/2006
476	Concrete Crusher	KDWM 2/14/2006
479	C-204 Disintegrator Building	KDWM 6/3/2002
481	C-410-A Hydrogen Holder	KDWM 4/2/2002
484	C-611-M Storage Tank	KDWM 8/30/2002
485	C-611-N Sanitary Water Storage	KDWM 2/18/2002
490	McGraw Fuel Facility Waste Oil Storage Tank	KDWM 12/21/2001
491	Mercury Spill at the C-611 Water Treatment Plant Vault	KDWM 3/22/2004
494	Ash Receiver Area in C-410/420	KDWM 6/3/2016; EPA 6/9/2016
495	C-410-I Ash Receiver Shed	KDWM 6/3/2016; EPA 6/92016
496	C-410 Fluorine/Hydrogen Filters (Northeast Mezzanine)	KDWM 6/320/16; EPA 6/9/2016
497	C-410/420 F ₂ Cell Neutralization Room Vats	KDWM 6/3/2016; EPA 6/9/2016
514	C-340 Magnesium Fluoride Reject Silo	EPA and KY 4/2/2015
515	C-340 "Dirty" Dust Collection System	EPA and KY 4/2/2015
516	C-340 Derby Preparation Area Sludge Collection System	EPA and KY 4/2/2015
519	C-410 Sulfuric Acid Tank (C-634-B)	KDWM 1/10/2003
521	C-340 Saw System Degreaser	EPA and KY 4/2/2015
525	Concrete Water Tower Supports (KOW)	KDWM 8/28/2007
527	C-410 GSA/SAA at Column J-6	KDWM 8/28/2007
528	GSA/SAA at the Northwest corner of C-745-G3 Paint Enclosure	KDWM 2/14/2006
530	Soil and Debris Storage Area by C-745-T Yard	KDWM 3/8/2007
532	Photographic Solution Treatment Area in the C-102 Building	KDWM 5/21/2003
534	UST #18, within SWMU 193	KDWM (UST Branch) 12/4/2007
535	S-755-T08-01 (Satellite Accumulation Area at C-755, Trailer 8)	KDWM 2/14/2006
536	Concrete Truck Washout Area	KDWM 6/27/2002
537	S-400-001 (SAA Located Outside at the Southeast Corner of the C-	KDWM 2/14/2006
	400 Building)	
538	S-MST-01-01 & S-MST-01-02 (Mobile Trailer 01)	KDWM 2/14/2006
539	S-MST-02-01 & S-MST-02-02 (Mobile Trailer 02)	KDWM 2/14/2006
540	S-MST-03-01 & S-MST-03-02 (Mobile Trailer 03)	KDWM 2/14/2006
542 A	G-746-B-01; S-746-B-01; S-746-B-02 (GSA/SAAs located outside	KDWM 1/28/2004
	C-746-A)	
542 B	G-746-A-01; S-746-A-01; S-746-A-02 (GSA/SAAs located outside	KDWM 1/28/2004
	C-746-A)	
543	T-746-S-01 (90-Day Storage Area)	KDWM 1/28/2004
544	T-752-C-01 (90-Day Storage Area)	KDWM 1/28/2004
545	C-755-T-22-01 and G-755-T-22	KDWM 1/28/2004
546	PGDP Post 67 Diesel Fuel Spill Area	KDWM 2/14/2006
547	PGDP Post 38 Diesel Spill Area	KDWM 2/14/2006
548	Staging Area for Concrete Piers, Wood and Rubble North Side of	KDWM 8/28/2007
	C-745-B Cylinder Yard	

Table A.1. Solid Waste Management Units/Areas of Concern by Operable Unit* (Continued)

	NO FURTHER ACTION (CONTINUED)				
SWMU No.	o. Description NFA Approval By				
551	C-755-GSA-23 Located at C-755 near the East Fence Line	KDWM 8/28/2007			
552	C-760 90-Day Accumulation Area	KDWM 3/28/2007			
566	H-340-01	KDWM 12/02/2010			
568	C-340 ST-90 Boxes	KDWM 12/02/2010			
569	C-743-T-17 Sample Return Refrigerator	KDWM 5/24/2012			
570	Sample Return Sealand	KDWM 5/24/2012			

Table A.1. Solid Waste Management Units/Areas of Concern by Operable Unit* (Continued)

PENDING NO FURTHER ACTION DECISION			
SWMU No.	Description		
	TBD		
SWN	IUs THAT WILL BE INVESTIGATED AND REMEDIATED BY THE U.S. ARMY CORPS OF ENGINEERS ¹¹		
94	KOW Trickling Filter and Leach Field		
95	KOW Burn Area		
157	KOW Toluene Spill Area		
182	Western Portion of Yellow Water Line		
CSOU = Comprehensive Site D&D = decontamination and EPA = U.S. Environmental F ER = environmental remedia FFA = Federal Facility Agree FY = fiscal year GDP = gaseous diffusion pla GSA = generator staging area HSWA = Hazardous and Sol HVAC = heating, ventilating KDWM = Kentucky Division KOW = Kentucky Ordinance	decommissioning rotection Agency tion ement nt a ad air-conditioning n of Waste Amendments , and air-conditioning n of Waste Management e Works t Discharge Elimination System tion Ditch myl iffusion Plant water a rea is Plan ement unit rable Unit ontrol Act tank		

¹¹ The Corps of Engineers accepted responsibility for the investigation/remediation of these SWMUs in a letter dated March 13, 1996. EPA review/approval of the CERCLA documentation (not yet available) associated with these SWMUs has not occurred.

	D	&D OU FACI	LITIES		
Facility Number	Description	SWMU/AOC Number	Facility Status	Integrated Site Evaluation (SE) Complete	CERCLA NTCRA Required
	Gaseous Diffusion Process F	acilities and Proc	ess Building Tie Li	nes and Bridges	
C-310	Purge and Product Building		Deactivating	No	Pending SE
C-310-A	Product Withdrawal Building		Deactivating	No	Pending SE
C-315	Surge and Waste Building		Deactivating	No	Pending SE
C-331	Process Building		Deactivating	No	Pending SE
C-333	Process Building		Deactivating	No	Pending SE
C-333-A	Feed Vaporization Facility	70	Deactivating	8/24/1987	Yes
C-335	Process Building		Deactivating	No	Pending SE
C-337	Process Building		Deactivating	No	Pending SE
C-337-A	Feed Vaporization Facility	71	Deactivating	8/24/1987	Yes
C-310-331	Tie-Line		Deactivating	No	Pending SE
C-310-331-A	Bridge (Enclosed)		Deactivating	No	Pending SE
С-310-331-В	Tie-Line		Deactivating	No	Pending SE
C-315-331	Tie-Line		Deactivating	No	Pending SE
C-331-333-A	Bridge (Enclosed-300 ft)		Deactivating	No	Pending SE
С-331-333-В	Tie-Line (West)		Deactivating	No	Pending SE
C-331-333-C	Tie-Line (East)		Deactivating	No	Pending SE
C-331-335	Tie-Line		Deactivating	No	Pending SE
C-335-337-A	Bridge (Enclosed)		Deactivating	No	Pending SE
С-335-337-В	Tie-Line (North)		Deactivating	No	Pending SE
С-335-337-С	Tie-Line (South)		Deactivating	No	Pending SE
	P	Process Support F	acilities	•	
C-409	Stabilization Building		Deactivating	No	Pending SE
C-415	Feed Plant Storage	482	Shutdown	7/18/2001	Yes
C-600	Steam Plant		Shutdown	No	Pending SE
		Switchyard	s		- -
C-531-1	Switch House	82	Operating	8/24/1987	Yes
C-531-2	Switchyard	82	Operating	8/24/1987	Yes
C-531-3A	Fire Valve House No. 1	82	Operating	8/24/1987	Yes
C-531-3B	Fire Valve House No. 2	82	Operating	8/24/1987	Yes
C-532	Relay House	82	Operating	8/24/1987	Yes
C-533-1	Switch House	83	Operating	8/24/1987	Yes
C-533-2	Switchyard	83	Operating	8/24/1987	Yes

D&D OU FACILITIES					
Facility Number	Description	SWMU/AOC Number	Facility Status	Integrated Site Evaluation (SE) Complete	CERCLA NTCRA Required
	S	witchyards (Con	tinued)		
C-533-3A	Fire Valve House No. 1	83	Operating	8/24/1987	Yes
C-533-3B	Fire Valve House No. 2	83	Operating	8/24/1987	Yes
C-533-3C	Fire Valve House No. 3	83	Operating	8/24/1987	Yes
C-533-3D	Fire Valve House No. 4	83	Operating	8/24/1987	Yes
C-535-1	Switch House	84	Operating	8/24/1987	Yes
C-535-2	Switchyard	84	Operating	8/24/1987	Yes
C-535-3A	Fire Valve House No. 1	84	Operating	8/24/1987	Yes
C-535-3B	Fire Valve House No. 2	84	Operating	8/24/1987	Yes
C-535-4	Test Shop (Maintenance Office)	84	Operating	8/24/1987	Yes
C-536	Relay House	84	Operating	8/24/1987	Yes
C-537-1	Switch House	85	Operating	8/24/1987	Yes
C-537-2	Switchyard	85	Operating	8/24/1987	Yes
C-537-3A	Fire Valve House No. 1	85	Operating	8/24/1987	Yes
С-537-3В	Fire Valve House No. 2	85	Operating	8/24/1987	Yes
C-537-3C	Fire Valve House No. 3	85	Operating	8/24/1987	Yes
C-537-3D	Fire Valve House No. 4	85	Operating	8/24/1987	Yes
C-537-4	Test Shop	85	Operating	8/24/1987	Yes
C-540-A	Oil Pump House	83	Operating	8/24/1987	Yes
C-541-A	Oil Pump House	84	Operating	8/24/1987	Yes
		Cooling Tow	ers		
C-631-1	Pump House	86	Operating	8/24/1987	Yes
C-631-2	Cooling Tower	86	Operating	8/24/1987	Yes
C-631-3	Fire Water Pump House	86	Operating	8/24/1987	Yes
C-631-4	Blending Pump House	86	Operating	8/24/1987	Yes
C-631-5	Blending Cooling Tower (West)	86	Operating	8/24/1987	Yes
C-631-6	Blending Cooling Tower (East)	86	Operating	8/24/1987	Yes
C-633-1	Pump House	87	Deactivating	8/24/1987	Yes
C-633-2A	Cooling Tower (South)	87	Deactivating	8/24/1987	Yes
C-633-2B	Cooling Tower (North)	87	Deactivating	8/24/1987	Yes
C-633-3	Blending Pump House	87	Deactivating	8/24/1987	Yes
C-633-4	Blending Cooling Tower (North)	87	Deactivating	8/24/1987	Yes
C-633-5	Blending Cooling Tower (South)	87	Deactivating	8/24/1987	Yes

D&D OU FACILITIES					
Facility Number	Description	SWMU/AOC Number	Facility Status	Integrated Site Evaluation (SE) Complete	CERCLA NTCRA Required
	Coo	oling Towers (Co	ontinued)		
C-633-6	Sand Filter Building	87	Deactivating	8/24/1987	Yes
C-635-1	Pump House	88	Deactivating	8/24/1987	Yes
C-635-2	Cooling Tower	88	Deactivating	8/24/1987	Yes
C-635-3	Blending Pump House	88	Deactivating	8/24/1987	Yes
C-635-4	Blending Cooling Tower (North)	88	Deactivating	8/24/1987	Yes
C-635-5	Blending Cooling Tower (South)	88	Deactivating	8/24/1987	Yes
C-637-1	Pump House	89	Deactivating	8/24/1987	Yes
C-637-2A	Cooling Tower (South)	89	Deactivating	8/24/1987	Yes
C-637-2B	Cooling Tower (North)	89	Deactivating	8/24/1987	Yes
C-637-3	Blending Pump House	89	Deactivating	8/24/1987	Yes
C-637-4	Blending Cooling Tower (North)	89	Deactivating	8/24/1987	Yes
C-637-5	Blending Cooling Tower (South)	89	Deactivating	8/24/1987	Yes
C-637-6	Sand Filter Building	89	Deactivating	8/24/1987	Yes
	Phosphate (Former	· Chromate) Red		llities	
C-616-A	Chemical Feed Building	42	Operating	12/18/91	Yes
C-616-B	Clarifier-East	42	Operating	12/18/91	Yes
C-616-C	Effluent Control Vault	42	Operating	12/18/91	Yes
C-616-D	Sludge Vault and Valve Pit	42	Operating	12/18/91	Yes
С-616-Н1	Ferrous Sulfate Storage Tank (East)	42	Operating	12/18/91	Yes
С-616-Н2	Ferrous Sulfate Storage Tank (West)	42	Operating	12/18/91	Yes
C-616-J	Reduction Tank (East)	42	Operating	12/18/91	Yes
C-616-K	Service Building	42	Operating	12/18/91	Yes
C-616-L	Lift Station	42	Operating	12/18/91	Yes
C-616-M	Clarifier (West)	42	Operating	12/18/91	Yes
C-616-N	Reduction Tank (West)	42	Operating	12/18/91	Yes
C-616-P	Sludge Vault and Valve Pit	42	Operating	12/18/91	Yes
		ewage System Fa			
C-615-A	Primary Settling Tank/Catch Basin	38	Operating	8/24/87	Yes
С-615-В	Final Settling Tank/Catch Basin	38	Operating	8/24/87	Yes
C-615-C	Sewage Plant Monitoring Building	38	Operating	8/24/87	Yes
C-615-D	Digester	38	Operating	8/24/87	Yes
С-615-Е	Trickling Filter	38	Operating	8/24/87	Yes
C-615-F	Dry Bed for Trickling Filter	38	Operating	8/24/87	Yes

	D&D OU FACILITIES					
Facility Number	Description	SWMU/AOC Number	Facility Status	Integrated Site Evaluation (SE) Complete	CERCLA NTCRA Required	
Process Laboratory and Maintenance Facilities						
C-709	Plant Laboratory Annex		Operating	No	Pending SE	
C-710	Technical Services Building/Lab		Operating	No	Pending SE	
C-720	Maintenance and Storage Building		Operating	No	Pending SE	
C-724-A	Carpenter Shop Annex	178	Operating	01/25/93	Yes	
C-726	Sandblast Building	172	Standby	10/29/92	Yes	
C-728	Motor Cleaning Facility	33	Operating	6/2/15	Yes	

AOC = area of concern

D&D = Decontamination and Decommissioning

CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act

NTCRA = non-time-critical removal action

SE = site evaluation

SWMU = solid waste management unit


Operating-Facility is currently in use supporting U.S. Department of Energy mission activities.


Standby-Facility is currently not in use but may be utilized to support future U.S. Department of Energy mission activities.

Shutdown-Facility is not being maintained for future use but has not yet begun deactivation activities.

Deactivating-Deactivation activities have been initiated.

Deactivation Complete—Awaiting decommissioning.





APPENDIX B

U.S. DEPARTMENT OF ENERGY CONTRACTOR PROCEDURES

Project-Wide Proced Procedure Number	Procedure Title	Commonto	
		Comments	
PAD-REG-1005	Spill Prevention, Control, and Countermeasure Plan for the U.S. Department of Energy Paducah Site, McCracken	D&R Contractor Program	
CDD D L 0044	County, Kentucky		
CP2-RA-0014	Environmental Compliance and Protection Program	D&R Contractor Program	
	Description at the Paducah Gaseous Diffusion Plant,		
CP2-RA-0015	Paducah, Kentucky Paducah Gaseous Diffusion Plant Facility Response Plan in	D&R Contractor Plan	
	Accordance with the Oil Pollution Act of 1990		
CP2-ES-0005	Pollution Prevention/Waste Minimization Plan for the Deactivation and Remediation Project, Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	
CP2-HS-2000	Worker Safety and Health Program for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Plan	
CP2-QA-1000	Quality Assurance Program Description for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Plan	
CP2-SM-1000	Activity Level Work Planning and Control Program for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	
SST-06.01.01	Paducah Work Control Process	SST Procedure	
CP2-EN-0201	Configuration Management Program Description at the Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	
CP3-OP-1118	Facility Management	D&R Contractor Procedure	
CP3-QA-1006	Suspect/Counterfeit Items	D&R Contractor Procedure	
	, and Health Procedures	~	
Procedure Number	Procedure Title	Comments	
CP1-HS-1000	Integrated Safety Management System Description for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Policy	
CP2-HS-2000	Worker Safety and Health Program for the Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	
CP3-EN-0227	Trenching, Excavation, and Penetration Permit	D&R Contractor Procedure	
CP3-HS-2003	Hazard Communication	D&R Contractor Procedure	
CP3-FR-2006	Fire Hazard Analysis and Facility Assessment	D&R Contractor Procedure	
CP3-FP-2005	Welding, Burning, and Hotwork	D&R Contractor Procedure	
SST-03.02.06	Welding, Burning, and Hotwork	SST Procedure	
SST-03.02.11	Defective Equipment Tags	SST Procedure	
SST-03.02.12	Confined Space Program	SST Procedure	
SST-03.02.02 SST-11.02.03	Excavation-Penetration Activities	SST Procedure	
CP3-HS-2010	Instructions for Lockout/Tagout	D&R Contractor Procedure	
CP3-HS-2008	Accident Prevention Equipment Control Tags	D&R Contractor Procedure	
Uranium Program P		Bur contactor i loculuit	
Procedure Number	Procedure Title	Comments	
DUF6-BWCS-PLN-	Paducah Groundwater Protection Plan	MCS/DUF6 Plan	
117			
DUF6-PLN-079	Paducah Storm Water Pollution Prevention and Best	MCS/DUF6 Plan	

Table B.1. U.S. Department of Energy Contractor Procedures

Transportation Proc Procedure Number	Procedure Title	Comments	
DUF6-U-WMP- 2001	Shipping	MCS/DUF6 Procedure	
DUF6-U-WMP- 2003	Hydrogen Fluoride (HF) Shipping	MCS/DUF6 Procedure	
CP2-WM-0025	Four Rivers Nuclear Partnership, LLC, Paducah Deactivation and Remediation Project Transportation Security Plan for the Transport of Hazardous Materials in Commerce	D&R Contractor Program	
CP2-WM-0661	Four Rivers Nuclear Partnership, LLC, Paducah Deactivation and Remediation Project Transportation Safety Document for On-Site Transport	D&R Contractor Plan	
Waste Management	Procedures		
Procedure Number	Procedure Title	Comments	
CP2-WM-0001	Four Rivers Nuclear Partnership, LLC Paducah Deactivation and Remediation Project Waste Management Plan	D&R Contractor Plan	
CP3-WM-1017	Safe Handling and Opening of Sealed Containers	D&R Contractor Procedure	
CP3-WM-1037	Generation and Temporary Storage of Waste Materials	D&R Contractor Procedure	
CP3-QA-2501	Waste Certification	D&R Contractor Procedure	
CP3-QA-2500	Procurement, Inspection, and Management of Items Critical for Paducah Off-Site Waste Shipments	D&R Contractor Procedure	
SST-03.06.01	Storage and Disposition of Spent Materials	SST Procedure	
CP3-WM-3015	Waste Packaging	D&R Contractor Procedure	
Data and Sampling H	Procedures		
Procedure Number	Procedure Title	Comments	
CP2-ES-0811	Pesticide and PCB Analyses Data Verification and Validation, Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	
CP4-ES-2708	Chain-of-Custody Forms, Field Sample Logs, Sample D&R Contractor I Labels, and Custody Seals		
CP3-ES-5003	Quality Assured Data	D&R Contractor Procedure	
CP4-ES-5004	Sample Tracking, Lab Coordination, and Sample Handling	D&R Contractor Procedure	
CP4-ES-5007	Data Management Coordination	D&R Contractor Procedure	
CP2-ES-5102	Radiochemical Analysis Data Verification and Validation, Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	

Table B.1. U.S. Department of Energy Contractor Procedures (Continued)

Data and Sampling Procedures (Continued)			
Procedure Number	Procedure Title	Comments	
CP2-ES-5103	Polychlorinated Dibenzodioxins/Polychlorinated Dibenzofurans Analyses Data Verification and Validation, Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	
CP2-ES-5105	Volatile and Semivolatile Analyses Data Verification and Validation, Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	
CP2-ES-5107	Inorganic Analyses Data Verification and Validation, Paducah Gaseous Diffusion Plant, Paducah, Kentucky	D&R Contractor Program	

Table B.1. U.S. Department of Energy Contractor Procedures (Continued)